TABLE OF CONTENTS

CITY OF SPOKANE STANDARD PLANS – SECTION V


B-101B = Revised Standard Plan

Back to Main TOC

***W-108A = New Standard Plan

#A-1 = Renumbered Standard Plan

<u>Plan No.</u>	<u>Plan Title</u>	Current Plan Date
V-101	Tree Planting Details All Types, Forms, and Species	5/15
V-102	Shrub Planting Details All Types, Forms, and Species	5/15
V-103	Irrigation System Details	2/86
V-104	2" and Smaller Meter/Backflow Assembly for Irrigation System	s8/19



NOTES:

- 1. TREES BURIED TOO DEEP, OR WITHOUT EXPOSING ROOT FLARE WILL BE REJECTED & SHALL BE REMOVED & REPLANTED AT PROPER DEPTH.
- 2. ALL 'ADVENTITIOUS ROOTS' AND 'SUCKERS' SHALL BE PRUNED AWAY PRIOR TO PLANTING.
- 3. DEVIATIONS FROM THIS DETAIL SHALL ONLY BE ALLOWED WITH PERMISSION FROM THE CITY ARBORIST.
- 4. TREES NOT PLANTED IN CONFORMITY WITH THIS DETAIL WILL BE REJECTED BY THE CITY ARBORIST. REPLACEMENT OF REJECTED TREES WILL BE DONE AT THE CONTRACTOR'S EXPENSE & NOT BY THE CITY OF SPOKANE.
- 5. LOCATIONS OF TREES TO MEET THE REQUIREMENTS OF DESIGN STANDARDS 3.5-2. ≥15 FT FROM DRIVEWAYS, ≥10 FT FROM DRAINAGE INLETS, ≥ 20 FT FROM DRYWELLS, NOT OBSTRUCT TRAFFIC SIGNS OR SIGHT TRIANGLES, AND 15 FT FROM UNDERGROUND UTILITIES
- 6. AFTER PLANTING, IF TREES ARE UNSTABLE, STAKING MAY BE USED BUT ONLY AS NECESSARY. AT 6 MONTHS, ALL STAKING MATERIAL SHALL BE REMOVED. IF TREE IS STILL UNSTABLE, AFTER 6 MONTHS, TREE MAY NEED TO BE REPLACED.


MLD

APPROVED BY	ADOPTED: REVISED:	2/1986 05/2015
	SUPERSEDES:	04/2012
ENGINEERING OPERATIONS MANAGER KYLE TWOHIG	CHECKED BY:	SJS
VATOUROS	SCALE:	NTS
PRINCIPAL ENCINEER CONST. VENNETH M. RROWN D.F.	REVISED BY:	MLD

TREE PLANTING DETAILS ALL TYPES, FORMS AND SPECIES



STANDARD PLAN No. V-101



NOTES:

- 1. SHRUBS BURIED TOO DEEP, OR WITHOUT EXPOSING ROOT FLARE WILL BE REJECTED & SHALL BE REMOVED & REPLANTED AT PROPER DEPTH.
- DEVIATIONS FROM THIS DETAIL SHALL ONLY BE ALLOWED WITH PERMISSION FROM THE CITY ARBORIST.
- 3. SHRUBS NOT PLANTED IN CONFORMITY WITH THIS DETAIL WILL BE REJECTED BY THE CITY ARBORIST. REPLACEMENT OF REJECTED SHRUBS WILL BE DONE AT THE CONTRACTOR'S EXPENSE & NOT BY THE CITY OF SPOKANE.


APPROV	ED BY
	1
ENGINEERING OPERATIONS MANA	GER KYLE TWOHIG
KATOUS	1
PRINCIPAL ENGINEER, CONST.	KENNETH M. BROWN, P.E.

ADOPTED:	2/1986
REVISED:	05/2015
SUPERSEDES:	04/2012
CHECKED BY:	SJS
SCALE:	NTS
REVISED BY:	MLD

SHRUB PLANTING DETAILS ALL TYPES, FORMS AND SPECIES




STANDARD PLAN No. V-102



POP-UP SPRINKLER DETAIL

TRIPLE SWING JOINTS




APPROVED BY CITY ENGR. Bed a Be. CH. DES. ENGR. THE

SCALE _ NONE ADOPTED _2-86

IRRIGATION SYSTEM DETAILS

REVISED --

DEPT. OF PUBLIC WORKS ENGR. DIVISION SPOKANE, WN. STANDARD PLAN No. v-103



NOTES:

- 1. CONTRACTOR IS TO PROVIDE ALL EXCAVATION AND BACKFILL FOR CITY FORCES TO SUPPLY AND INSTALL, UPON PAYMENT OF FEES, THE TAPPING SADDLE, CORP STOP, SERVICE LINE, CURB STOP, METER VAULT, METER & ISOLATION VALVES INSIDE METER VAULT. TRENCH EXCAVATION AND BACKFILL PAID UNDER BID ITEM TRENCH EXCAVATION FOR WATER SERVICE TAP.
- 2. CONTRACTOR IS FULLY RESPONSIBLE FOR FURNISHING AND INSTALLING ALL PIPE & FITTINGS DOWNSTREAM OF THE METER VAULT.
- 3. ALL PIPE & FITTINGS DOWNSTREAM OF THE METER TO THE MAINLINE TO BE GALVANIZED SCH. 40.
- 4. CITY TO SUPPLY AND INSTALL PRV INSIDE OF METER VAULT WHERE PRESSURES EXCEED 80 PSI.
- 5. SEE IRRIGATION DESIGN GUIDELINES FOR ADDITIONAL INSTALLATION INFORMATION.



2" AND SMALLER METER/BACKFLOW ASSEMBLY FOR IRRIGATION SYSTEMS



ENGINEERING SERVICES CITY OF SPOKANE, WASHINGTON

STANDARD PLAN No. V-104