

TABLE OF CONTENTS


CITY OF SPOKANE STANDARD PLANS – SECTION Y

B-101B = Revised Standard Plan
 ***W-108A = New Standard Plan
 #A-1 = Renumbered Standard Plan

[Back to Main TOC](#)

<u>Plan No.</u>	<u>Plan Title</u>	<u>Current Plan Date</u>
Y-101	Hydrant Setting – Standard	7/20
Y-101A	Hydrant Setting – Offsets	7/20
Y-102	2" Air Valve for Ductile Iron Pipe	4/21
Y-103	Drywell Blow-off – Interior 4" Gate Valve	4/21
Y-103A	Drywell Blow-off – Exterior 4" Gate Valve	4/21
Y-104	Manhole Blow-off – Interior 4" Gate Valve	4/21
Y-105	Pumper Style Blow-off – Interior 4" Gate Valve	4/21
Y-105A	Pumper Style Blow-off - Exterior 4" Gate Valve	4/21
Y-108	Typical Ductile Iron Pipe Clamp for Pipe Up to 12" Dia	2/86
Y-109	Cast Iron Valve Box	4/21
Y-110	See Std. Plan A-9	
Y-111	Typical 1-2" Water Service	4/21
Y-112	PVC Water Meter Box – Typical Installation	4/21
Y-112A	Concrete Water Meter Box – Typical Installation	4/21
Y-113	48" Meter Vault	4/21
Y-114	48" Precast Concrete Vault	4/21
Y-115	Water Service Vault – Minimum Dimensions	7/20
Y-116	Water Meter Vault – Small	4/21
Y-117	Water Meter Vault – Large	4/21
Y-118	Domestic/Fire Line, 4" – 10" Service – Double Check Valve Assembly	4/21
Y-119	Irrigation Service with DCVA, 3" – 6"	4/21
Y-120	Domestic/Fire Line, 4" – 6", 8" or 10" – Service Reduced Pressure Assembly	4/21


SEE SEC. 9-30.5 OF
STANDARD SPECIFICATIONS




PROFILE


NOTES:

- 1. WATER DISTRIBUTION MATERIALS AND APPURTENANCES SHALL CONFORM TO SEC 9-30.
- 2. SEE SECTION 9-33 FOR WOVEN GEOTEXTILE FABRIC (MODERATE SURVIVABILITY, CLASS A). OVERLAP ALL FABRIC JOINTS 1'-6" MIN. WRAP AND SECURE FABRIC AROUND PIPE TO PREVENT MIGRATION OF FINES INTO GRAVEL ENVELOPE.
- 3. SEE SECTION 9-03.12(5) FOR GRAVEL BACKFILL FOR DRYWELLS.
- 4. SEE COS GSP SPEC 7-14.3 FOR FIRE HYDRANT PLACEMENT DISTANCE FROM CURB RAMPS AND DRIVEWAYS.
- 5. MAINTAIN MINIMUM 3' DISTANCE FROM HYDRANT TO TRAVELED ROADWAY OR CURB.
- 6. MINIMUM 3' CLEAR TO OBSTRUCTIONS REQUIRED FOR OPERATING NUT AND STORZ FITTING.
- 7. STORZ FITTING REQUIRED ON SITE PRIOR TO INSTALLATION.

<div>APPROVED BY</div> <div></div> <div>ENGINEERING SERVICES DIRECTOR KYLE TWOHIG</div> <div>CHTY ENGINEER DAN BULLER, P.E.</div>	<div>ADOPTED: _____</div> <div>REVISED: 07/2020</div> <div>SUPERSEDES: 02/2017</div> <div>SCALE: _____ NTS</div> <div>DWG./REV BY: MB/MLD</div>	<div>HYDRANT SETTING STANDARD</div> <div>ENGINEERING SERVICES CITY OF SPOKANE, WASHINGTON</div> <div>STANDARD PLAN No. Y-101</div>
---	---	--



RAISED OFFSET



NOTES:

1. WATER DISTRIBUTION MATERIALS AND APPURTENANCES SHALL CONFORM TO SEC 9-30.
2. SEE SECTION 9-33 FOR WOVEN GEOTEXTILE FABRIC (MODERATE SURVIVABILITY, CLASS A). OVERLAP ALL FABRIC JOINTS 1'-6" MIN. WRAP AND SECURE FABRIC AROUND PIPE TO PREVENT MIGRATION OF FINES INTO GRAVEL ENVELOPE.
3. SEE SECTION 9-03.12(5) FOR GRAVEL BACKFILL FOR DRYWELLS.
4. SEE COS GSP SPEC 7-14.3 FOR HYDRANT PLACEMENT DISTANCE FROM CURB RAMPS & DRIVEWAYS. MAINTAIN MIN 3' HYDRANT PLACEMENT DISTANCE FROM TRAVELED ROADWAYS & CURBS. MIN 3' CLEAR TO OBSTRUCTIONS REQUIRED FOR OPERATING NUT AND STORZ FITTING

DEPRESSED OFFSET

APPROVED BY

ENGINEERING SERVICES DIRECTOR KYLE TWOHIG
CITY ENGINEER DAN BULLER, P.E.



ADOPTED: _____
REVISED: 07/2020
SUPERSEDES: 02/2017
SCALE: NTS
DWG./REV BY: MB/MLD

HYDRANT SETTING OFFSETS



ENGINEERING SERVICES
CITY OF SPOKANE, WASHINGTON

STANDARD
PLAN No.
Y-101A



NOTES:

1. SEE SEC. 7-100 FOR VALVE CHAMBERS, & SEC. 9-12.4 FOR PRECAST CONCRETE MANHOLES.
2. SEE SECS. 7-12 & 9-30 FOR WATER FITTINGS.
3. SEE STD PLANS A-12 (BY DEFAULT) & A-13 (IF LOCATED IN ARTERIAL STREET) FOR MANHOLE FRAME & COVER.
4. SEE STD PLAN Z-101 FOR MANHOLE - 48" & Z-102 FOR MANHOLE - 54".
5. SEE STD PLAN Z-108 FOR MANHOLE TOP SLAB REINFORCEMENT DETAILS.
6. TOP SLAB & BARREL JOINT(S) MAY BE EITHER TONGUE & GROOVE OR REVERSE TONGUE & GROOVE.
7. ADJUSTMENT SECTION, TOP SLAB, & BARREL JOINT(S) TO BE SEALED PER SECS. 7-05 & 9-04.
8. USE MANHOLE - 48" W/ CONCENTRIC CONE TOP WHEN VERTICAL CLEARANCE IS ADEQUATE. USE MANHOLE - 54" W/ TOP SLAB AS SHOWN ABOVE, WHEN VERTICAL CLEARANCE IS MINIMAL.
9. ADJUSTMENT SECTION HEIGHT FOR EXISTING STRUCTURES TO MATCH FIELD CONDITIONS AS REQ'D (3" MIN-16" MAX)

APPROVED BY

ENGINEERING SERVICES DIRECTOR
KYLE TWOHIG
CITY ENGINEER
DAN BULLER, P.E.


ADOPTED: _____
REVISED: 4/2021
SUPERSEDES: 10/2019
CHECKED BY: JAG
SCALE: NTS
REVISED BY: SRM/MLD

**2" AIR VALVE
FOR DUCTILE IRON PIPE**



ENGINEERING SERVICES
CITY OF SPOKANE, WASHINGTON

STANDARD
PLAN No.
Y-102




NOTES:

1. SEE SEC 9-12 FOR PRECAST CONCRETE DRYWELLS.
2. SEE SEC 9-03.12(5) FOR GRAVEL BACKFILL FOR DRYWELLS.
3. SEE SEC 9-33 FOR WOVEN GEOTEXTILE FABRIC (MODERATE SURVIVABILITY, CLASS A). OVERLAP ALL FABRIC JOINTS 1'-6" MIN. WRAP & SECURE FABRIC AROUND PIPE TO PREVENT MIGRATION OF FINES INTO GRAVEL ENVELOPE.
4. SEE STD PLANS A-12 (BY DEFAULT) & A-13 (IF LOCATED IN ARTERIAL STREET) FOR MANHOLE FRAME & COVER.
5. SEE STD PLANS B-102C & Z-118 FOR BASE & FOUNDATION DETAILS.
6. CONE & BARREL JOINTS MAY BE EITHER TONGUE & GROOVE OR REVERSE TONGUE & GROOVE.
7. ADJUSTMENT SECTION, CONE & BARREL JOINTS TO BE SEALED PER SEC 7-05.
8. ONE DRYWELL MAY SERVE MORE THAN ONE INTERIOR BLOW-OFF VALVE.
9. ADJUSTMENT SECTION HEIGHT FOR EXISTING STRUCTURES TO MATCH FIELD CONDITIONS AS REQUIRED SEE STANDARD PLAN A-8.
10. WATER DISTRIBUTION MATERIALS AND APPURTENANCES SHALL CONFORM TO SEC 9-30.
11. ALL JOINTS SHALL BE RESTRAINED JOINTS PER SEC 9-30.

SECTION

<p>APPROVED BY</p> <p>ENGINEERING SERVICES DIRECTOR KYLE TWOHIG</p> <p>CITY ENGINEER DAN BULLER, P.E.</p>	<p>ADOPTED: _____</p> <p>REVISED: 4/2021</p> <p>SUPERSEDES: 10/2019</p> <p>SCALE: NTS</p> <p>DWG/REV. BY: SRM/MLD</p>	<div style="text-align: center;"> <p>DRYWELL BLOW-OFF</p> <p>INTERIOR 4" GATE VALVE</p> </div> <div style="display: flex; justify-content: space-between; align-items: center;"> <div style="text-align: center;"> <p>ENGINEERING SERVICES</p> <p>CITY OF SPOKANE, WASHINGTON</p> </div> <div style="text-align: right;"> <p>STANDARD PLAN No.</p> <p>Y-103</p> </div> </div>
---	---	--



NOTES:

1. SEE SEC 9-12 FOR PRECAST CONCRETE DRYWELLS.
2. SEE SEC 9-03.12(5) FOR GRAVEL BACKFILL FOR DRYWELLS.
3. SEE SEC 9-33 FOR WOVEN GEOTEXTILE FABRIC (MODERATE SURVIVABILITY, CLASS A). OVERLAP ALL FABRIC JOINTS 1 WRAP & SECURE FABRIC AROUND PIPE TO PREVENT MIGRATION OF FINES INTO GRAVEL ENVELOPE.
4. SEE STD PLANS A-12 (BY DEFAULT) & A-13 (IF LOCATED IN ARTERIAL STREET) FOR MANHOLE FRAME & COVER.
5. SEE STD PLANS B-102C & Z-118 FOR BASE & FOUNDATION DETAILS.
6. CONE & BARREL JOINTS MAY BE EITHER TONGUE & GROOVE OR REVERSE TONGUE & GROOVE.
7. ADJUSTMENT SECTION, CONE & BARREL JOINTS TO BE SEALED PER SEC 7-05.
8. ONE DRYWELL MAY SERVE MORE THAN ONE INTERIOR BLOW-OFF VALVE.
9. ADJUSTMENT SECTION HEIGHT FOR EXISTING STRUCTURES TO MATCH FIELD CONDITIONS AS REQUIRED SEE STANDARD PLAN A-8.
10. WATER DISTRIBUTION MATERIALS AND APPURTENANCES SHALL CONFORM TO SEC 9-30.
11. ALL JOINTS SHALL BE RESTRAINED JOINTS PER SEC 9-30.

SECTION

APPROVED BY

ENGINEERING SERVICES DIRECTOR
KYLE TWOHIG
CITY ENGINEER
DAN BULLER, P.E.


ADOPTED: _____
REVISED: 4/2021
SUPERSEDES: 10/2019
SCALE: NTS
DWG/REV. BY: SRM/MLD

**DRYWELL BLOW-OFF
EXTERIOR 4" GATE VALVE**



ENGINEERING SERVICES
CITY OF SPOKANE, WASHINGTON

STANDARD
PLAN No.
Y-103A



NOTES:

1. SEE SECTIONS 7-05 & 9-12.4 FOR PRECAST CONCRETE MANHOLES
2. SEE SECTIONS 7-12 & 9-30 FOR WATER FITTINGS.
3. SEE STD PLAN Z-109 FOR MANHOLE STEP DETAILS.
4. CONE & BARREL JOINTS MAY BE EITHER TONGUE & GROOVE OR REVERSE TONGUE & GROOVE.

APPROVED BY

ENGINEERING SERVICES DIRECTOR KYLE TWOHIG
CITY ENGINEER DAN BULLER, P.E.


ADOPTED: _____
REVISED: 4/2021
SUPERSEDES: 10/2019
CHECKED BY: JAG
SCALE: NTS
DWG/REV. BY: RLB/MLD

MANHOLE BLOW-OFF
INTERIOR 4" GATE VALVE



ENGINEERING SERVICES
CITY OF SPOKANE, WASHINGTON

STANDARD
PLAN No.
Y-104



SECTION

NOTES:

1. SEE SEC 9-12 FOR PRECAST CONCRETE MANHOLES.
2. SEE STD PLANS A-12 (BY DEFAULT) & A-13 (IF LOCATED IN ARTERIAL STREET) FOR MANHOLE FRAME & COVER.
3. SEE STD PLANS B-102C & Z-118 FOR BASE & FOUNDATION DETAILS.
4. CONE & BARREL JOINTS MAY BE EITHER TONGUE & GROOVE OR REVERSE TONGUE & GROOVE.
5. ADJUSTMENT SECTION, CONE & BARREL JOINTS TO BE SEALED PER SEC 7-05.
6. ONE MANHOLE MAY SERVE MORE THAN ONE INTERIOR BLOW-OFF VALVE.
7. ADJUSTMENT SECTION HEIGHT FOR EXISTING STRUCTURES TO MATCH FIELD CONDITIONS AS REQUIRED SEE STANDARD PLAN A-8.
8. WATER DISTRIBUTION MATERIAL AND APPURTENANCES SHALL CONFORM TO SEC 9-30.
9. ALL JOINTS SHALL BE RESTRAINED JOINTS PER SEC 9-30.

APPROVED BY

ENGINEERING SERVICES DIRECTOR KYLE TWOHIG
CITY ENGINEER DAN BULLER, P.E.

ADOPTED: _____
REVISED: 4/2021
SUPERSEDES: 10/2019
CHECKED BY: JTG
SCALE: NTS
DWG/REV. BY: LWK/MLD

PUMPER STYLE BLOW-OFF
INTERIOR 4" GATE VALVE



ENGINEERING SERVICES
CITY OF SPOKANE, WASHINGTON

STANDARD
PLAN No.
Y-105

NOTES:

1. SEE SEC 9-12 FOR PRECAST CONCRETE MANHOLES.
2. SEE STD PLANS A-12 (BY DEFAULT) & A-13 (IF LOCATED IN ARTERIAL STREET) FOR MANHOLE FRAME & COVER.
3. SEE STD PLANS B-102C & Z-118 FOR BASE & FOUNDATION DETAILS.
4. CONE & BARREL JOINTS MAY BE EITHER TONGUE & GROOVE OR REVERSE TONGUE & GROOVE.
5. ADJUSTMENT SECTION, CONE & BARREL JOINTS TO BE SEALED PER SEC 7-05.
6. ONE MANHOLE MAY SERVE MORE THAN ONE INTERIOR BLOW-OFF VALVE.
7. ADJUSTMENT SECTION HEIGHT FOR EXISTING STRUCTURES TO MATCH FIELD CONDITIONS AS REQUIRED
SEE STANDARD PLAN A-8
8. WATER DISTRIBUTION MATERIAL AND APPURTENANCES SHALL CONFORM TO SEC 9-30.
9. ALL JOINTS SHALL BE RESTRAINED JOINTS PER SEC 9-30.

ENGINEERING SERVICES DIRECTOR KYLE TWOHIG

CITY ENGINEER DAN BULLER, P.E.

ADOPTED: _____
 REVISED: 04/2021
 SUPERSEDES: 10/2019
 CHECKED BY: JTG
 SCALE: NTS
 DWG/REV. BY: LWK/MLD


PUMPER STYLE BLOW-OFF
EXTERIOR 4" GATE VALVE




ENGINEERING SERVICES
CITY OF SPOKANE, WASHINGTON

STANDARD
PLAN No.
Y-105A

Center Bolt Hole (Hole $\frac{7}{8}$ " Diameter)




SIDE VIEW




TOP VIEW


<p>APPROVED BY</p> <p>CITY ENGR <i>[Signature]</i></p> <p>CH. DES. ENGR. <i>[Signature]</i></p>	<p>SCALE <u>NONE</u></p> <p>ADOPTED <u>2-86</u></p> <p>REVISED <u>-----</u></p>	<p>TYPICAL DUCTILE IRON PIPE CLAMP FOR PIPE UP TO 12" DIA.</p> <p>DEPT. OF PUBLIC WORKS ENGR. DIVISION SPOKANE, WN.</p> <p>STANDARD PLAN No. Y-108</p>	
---	---	--	--



BOTTOM SECTION



COVER



TOP SECTION**

*OLYMPIC FOUNDRY MODEL 930 – 15" TOP, 5 1/4" HEAVY LID (OR APPROVED EQUAL)

**TOP SECTION & COVER TO ALSO BE USED TO PROTECT CURB
STOPS LOCATED IN PAVED OR CONCRETE AREAS

APPROVED BY

ENGINEERING SERVICES DIRECTOR
[Signature]
CITY ENGINEER

KYLE TWOHIG
[Signature]
DAN BULLER, P.E.

ADOPTED: _____
REVISED: 04/2021
SUPERSEDES: 02/2017


SCALE: NOT TO SCALE
DWG./REV BY: DGB/MLD




CAST IRON VALVE BOX*




ENGINEERING SERVICES
CITY OF SPOKANE, WASHINGTON

STANDARD
PLAN No.
Y-109






<p>APPROVED BY</p>  <p>ENGINEERING SERVICES DIRECTOR KYLE TWOHIG</p>  <p>CITY ENGINEER DAN BULLER, P.E.</p>	<p>ADOPTED: _____</p> <p>REVISED: 04/2021</p> <p>SUPERSEDES: 01/2017</p> <p>CHECKED BY: JTG</p> <p>SCALE: NTS</p> <p>DWG/REV. BY: ABM/MLD</p>	<p>TYPICAL 1-2" WATER SERVICE</p>  <p>ENGINEERING SERVICES CITY OF SPOKANE, WASHINGTON</p> <p>STANDARD PLAN No. Y-111</p>
---	---	--




NOTES:



- 1) IF CURB STOP IS NOT AT 5' DEPTH FROM FINISHED GRADE, SERVICE WILL NEED TO BE EXCAVATED 3-4' TOWARD THE STREET TO FACILITATE RAISING OR LOWERING CURB STOP, BY CITY FORCES, TO 5' DEPTH
- 2) EXCAVATION TO BE DONE BY CONTRACTOR PER L&I REGULATIONS
- 3) BEDDING MUST BE ON SITE, FILL IN 1' LIFTS TO AVOID OVALING
- 4) 5/8", 3/4", 1" T-10 METERS ONLY
- 5) BOX IS NOT TRAFFIC RATED, NOT TO BE INSTALLED IN SIDEWALKS, DRIVEWAYS OR STREETS
- 6) MUST BE AT FINISH GRADE FOR FINAL INSPECTION OR IT WILL NEED TO BE RESET


<p>APPROVED BY</p>  <p>ENGINEERING SERVICES DIRECTOR KYLE TWOHIG</p> <p>CITY ENGINEER DAN BULLER, P.E.</p>	<p>ADOPTED: _____</p> <p>REVISED: 04/2021</p> <p>SUPERSEDES: 01/2017</p> <p>CHECKED BY: JTG</p> <p>SCALE: NTS</p> <p>DWG/REV. BY: ABM/MLD</p>	<p>PVC WATER METER BOX TYPICAL INSTALLATION</p>  <p>ENGINEERING SERVICES CITY OF SPOKANE, WASHINGTON</p> <p>STANDARD PLAN No. Y-112</p>
---	---	--






- NOTES:
- 1) UP TO (2) 1" - 2" SERVICES & METERS PER VAULT
 - 2) DCVA WILL FIT VERTICALLY OR MAY BE PLACED OUTSIDE VAULT IN IRRIGATION BOX
 - 3) 1/2" CONDUIT TO BUILDING FOR WIRE IS REQUIRED

<p>APPROVED BY</p>  <p>ENGINEERING SERVICES DIRECTOR KYLE TWOHIG</p>		<p>ADOPTED: _____</p> <p>REVISED: 04/2021</p> <p>SUPERSEDES: 01/2017</p> <p>CHECKED BY: JTG</p> <p>SCALE: NTS</p> <p>DWG/REV. BY: ABM/MLD</p>		<p>48" METER VAULT</p>	
<p>CITY ENGINEER DAN BULLER, P.E.</p>		 <p>ENGINEERING SERVICES CITY OF SPOKANE, WASHINGTON</p>		<p>STANDARD PLAN No. Y-113</p>	




PLAN VIEW



SECTION VIEW

APPROVED BY

ENGINEERING SERVICES DIRECTOR

 KYLE TWOHIG
 CITY ENGINEER

 DAN BULLER, P.E.

ADOPTED: _____
 REVISED: 04/2021
 SUPERSEDES: 10/2019
 CHECKED BY: JTG
 SCALE: NTS
 DWG/REV. BY: ABM/MLD

48" PRECAST CONCRETE VAULT



ENGINEERING SERVICES
 CITY OF SPOKANE, WASHINGTON

STANDARD
 PLAN No.
Y-114

MINIMUM WATER SERVICE VAULT DIMENSIONS

	<u>W X L X H (INSIDE)</u>
3" DOMESTIC	6' X 8' X 6'6"
3" DOMESTIC W/DCVA	6' X 10' X 6'6"
3" IRRIGATION W/DCVA	6' X 10' X 6'6"
4" DOMESTIC	6' X 8' X 6'6"
4" DOMESTIC W/DCVA	6' X 10' X 6'6"
4" FIRE ONLY	6' X 7' X 6'6"
4" FIRE & DOMESTIC	6' X 12' X 6'6"
4" IRRIGATION W/DCVA	6' X 10' X 6'6"
6" DOMESTIC	6' X 8' X 6'6"
6" DOMESTIC W/DCVA	6' X 12' X 6'6"
6" FIRE ONLY	6' X 8' X 6'6"
6" FIRE & DOMESTIC	6' X 14' X 6'6"
6" IRRIGATION W/DCVA	6' X 12' X 6'6"
8" FIRE ONLY	6' X 10' X 6'6"
8" FIRE & DOMESTIC	6' X 16' X 6'6"
10" FIRE ONLY	6' X 10' X 6'6"
10" FIRE & DOMESTIC	6' X 16' X 6'6"



1. IF THERE ARE 2 SERVICES, (EG TWO LINES 4" AND LARGER OR THREE LINES 2" AND LARGER RUNNING PARALLEL IN VAULT) ALL VAULTS SHALL BE A MINIMUM OF 8' WIDE.

2. IF THERE ARE MORE THAN 2 SERVICES, VAULT DIMENSIONS MUST BE OBTAINED FROM THE TAPPING DEPARTMENT (509) 625-7847

3. ALL VAULTS WILL BE HEAVY DUTY TRAFFIC RATED

4. THESE VAULTS ARE MINIMUM INSIDE DIMENSIONS

APPROVED BY



ENGINEERING SERVICES DIRECTOR KYLE TWOHIG

CITY ENGINEER DAN BULLER, P.E.

ADOPTED: _____
REVISED: 07/2020
SUPERSEDES: 02/2017
SCALE: _____ NTS
DWG./REV BY: MB/MLD

WATER SERVICE VAULT MINIMUM DIMENSIONS

ENGINEERING SERVICES
CITY OF SPOKANE, WASHINGTON

STANDARD
PLAN No.
Y-115



- ①A FIRE LINE OSY, INLET
- ①B FIRE LINE OSY, OUTLET
- ② DCDVA W/ 5/8" T-10 METER
- ③ DUCTILE IRON PIPE
- ④ DOMESTIC SERVICE
- ⑤ IRRIGATION SERVICE
- ⑥ CURB STOP
- ⑦A INLET VALVE, DOMESTIC/IRRIGATION
- ⑦B OUTLET VALVE, DOMESTIC/IRRIGATION
- ⑧A NEPTUNE TRUFLOW METER
- ⑧B IRRIGATION METER

- ⑨A DCVA ON ALL COMMERCIAL APPLICATIONS AND RESIDENTIAL WHERE REQUIRED
- ⑨B BACKFLOW ASSEMBLY, IRRIGATION
- ⑩ VAULT (PER Y-115) PROVIDED AND INSTALLED BY CONTRACTOR
- ⑪ TEE OR TAPPING SADDLE
- ⑫ POST INDICATOR (THROUGH VAULT TOP)
- ⑬ CHECK WITH BALL DRIP
- ⑭ PUMPER CONNECTION (FDC) (THROUGH VAULT)
- ⑮ 3/4" ELECTRICAL CONDUIT FOR REMOTE READER, VAULT TO BUILDING OR BOLLARD (36" ABOVE GROUND), ETC
- ⑯ TAP PERMIT REQUIRED

NOTES:

1. ALL EXCAVATION, BEDDING, BACKFILL, & RESTORATION, INCLUDING FOR CITY INSTALLED PIPING, IS TO BE DONE BY CONTRACTOR.
2. IN SHALLOW GROUNDWATER AREAS WHERE SEASONAL HIGH LEVEL WILL REACH BOTTOM OF VAULT OR IS <7' DEEP, METER VAULT SHALL BE ONE OF THE FOLLOWING:

a) BUOYANT RESISTANT VAULT WITH WATERTIGHT JOINTS AND PIPE PENETRATIONS, AND EXTERIOR WATER PROOF COATING (XYPEX OR EQUIVALENT). MIN 12" WIDE BY 6" DEEP SUMP TO BE PROVIDED FOR PUMP OUT. BOLTS FOR FLANGES AND MJ FITTINGS SHALL BE ASTM 316.

b) BE LOCATED ABOVE GROUND IN THE HEATED AND INSULATED ENCLOSURE SUCH AS HOTBOX MOUNTED ON MIN 6" THICK REINFORCED CONCRETE BASE.


APPROVED BY

 ENGINEERING SERVICES DIRECTOR KYLE TWOHIG

 CITY ENGINEER DAN BULLER, P.E.

ADOPTED: _____
 REVISED: 04/2021
 SUPERSEDES: 07/2020
 CHECKED BY: DCS
 SCALE: NTS
 DWG/REV. BY: ABM/MLD

WATER METER VAULT SMALL	
ENGINEERING SERVICES CITY OF SPOKANE, WASHINGTON	STANDARD PLAN No. Y-116



- ①A FIRE LINE OSY, INLET
- ①B FIRE LINE OSY, OUTLET
- ② DCDVA W/ 5/8" T-10 METER
- ③ DUCTILE IRON PIPE
- ④ DOMESTIC SERVICE
- ⑤ IRRIGATION SERVICE
- ⑥ CURB STOP
- ⑦A INLET VALVE, DOMESTIC/IRRIGATION
- ⑦B OUTLET VALVE, DOMESTIC/IRRIGATION
- ⑧A NEPTUNE TRUFLOW METER
- ⑧B IRRIGATION METER

- ⑨A DCVA ON ALL COMMERCIAL APPLICATIONS AND RESIDENTIAL WHERE REQUIRED
- ⑨B BACKFLOW ASSEMBLY, IRRIGATION
- ⑩ VAULT (PER Y-115) PROVIDED AND INSTALLED BY CONTRACTOR
- ⑪ TEE OR TAPPING SADDLE
- ⑫ POST INDICATOR (THROUGH VAULT TOP)
- ⑬ CHECK WITH BALL DRIP
- ⑭ PUMPER CONNECTION (FDC) (THROUGH VAULT)
- ⑮ 3/4" ELECTRICAL CONDUIT FOR REMOTE READER, VAULT TO BUILDING OR BOLLARD (36" ABOVE GROUND), ETC
- ⑯ TAP PERMIT REQUIRED

NOTES:

1. ALL EXCAVATION, BEDDING, BACKFILL, & RESTORATION, INCLUDING FOR CITY INSTALLED PIPING, IS TO BE DONE BY CONTRACTOR.
2. IN SHALLOW GROUNDWATER AREAS WHERE SEASONAL HIGH LEVEL WILL REACH BOTTOM OF VAULT OR IS <7' DEEP, METER VAULT SHALL BE ONE OF THE FOLLOWING:

a) BUOYANT RESISTANT VAULT WITH WATERTIGHT JOINTS AND PIPE PENETRATIONS, AND EXTERIOR WATER PROOF COATING (XYPEX OR EQUIVALENT). MIN 12" WIDE BY 6" DEEP SUMP TO BE PROVIDED FOR PUMP OUT. BOLTS FOR FLANGES AND MJ FITTINGS SHALL BE ASTM 316.

b) BE LOCATED ABOVE GROUND IN THE HEATED AND INSULATED ENCLOSURE SUCH AS HOTBOX MOUNTED ON MIN 6" THICK REINFORCED CONCRETE BASE.

APPROVED BY

 ENGINEERING SERVICES DIRECTOR KYLE TWOHIG


 CITY ENGINEER DAN BULLER, P.E.

ADOPTED: _____
 REVISED: 04/2021
 SUPERSEDES: 07/2020
 CHECKED BY: JTG
 SCALE: NTS
 DWG/REV. BY: ABM/MLD



**WATER METER VAULT
 LARGE**
 ENGINEERING SERVICES
 CITY OF SPOKANE, WASHINGTON

STANDARD
 PLAN No.
Y-117



SITE NOTES:

IN SHALLOW GROUNDWATER AREAS WHERE SEASONAL HIGH LEVEL WILL REACH BOTTOM OF VAULT OR IS <7' DEEP, METER VAULT SHALL BE ONE OF THE FOLLOWING:

- A) BUOYANT RESISTANT VAULT WITH WATERTIGHT JOINTS AND PIPE PENETRATIONS, AND EXTERIOR WATER PROOF COATING (XYPEX OR EQUIVALENT). MIN 12" WIDE BY 6" DEEP SUMP TO BE PROVIDED FOR PUMP OUT. BOLTS FOR FLANGES AND MJ FITTINGS SHALL BE ASTM 316.
- B) BE LOCATED ABOVE GROUND IN THE HEATED AND INSULATED ENCLOSURE SUCH AS HOTBOX MOUNTED ON MIN 6" THICK REINFORCED CONCRETE BASE.

VAULT NOTES:

- 1) TRAFFIC RATED LID
- 2) OPEN BOTTOM UNLESS IN HIGH GROUNDWATER AREAS, SEE SITE NOTE
- 3) DIMENSION BASED ON: WATTS 709 DCVA
NEPTUNE HP PROTECTUS III METER
- 4) EXCAVATION, BEDDING, BACKFILL & SURFACE RESTORATION TO BE DONE BY CONTRACTOR PER L&I REGULATIONS
- 5) 3/4" MIN CONDUIT REQUIRED FOR REMOTE READER, VAULT TO BUILDING OR BOLLARD (36" ABOVE GROUND), ETC
- 6) VAULT SIZE PER Y-115

APPROVED BY

 ENGINEERING SERVICES DIRECTOR KYLE TWOHIG
 CITY ENGINEER DAN BULLER, P.E.


ADOPTED: _____
 REVISED: 04/2021
 SUPERSEDES: 07/2020
 CHECKED BY: JTG
 SCALE: NTS
 DWG/REV. BY: ABM/MLD

**DOMESTIC/FIRELINE 4"-10" SERVICE
DOUBLE CHECK VALVE ASSEMBLY**



ENGINEERING SERVICES
CITY OF SPOKANE, WASHINGTON

STANDARD
PLAN No.
Y-118



SITE NOTES:

IN SHALLOW GROUNDWATER AREAS WHERE SEASONAL HIGH LEVEL WILL REACH BOTTOM OF VAULT OR IS <7' DEEP, METER VAULT SHALL BE ONE OF THE FOLLOWING:

- A) BUOYANT RESISTANT VAULT WITH WATERTIGHT JOINTS AND PIPE PENETRATIONS, AND EXTERIOR WATER PROOF COATING (XYPEX OR EQUIVALENT). MIN 12" WIDE BY 6" DEEP SUMP TO BE PROVIDED FOR PUMP OUT. BOLTS FOR FLANGES AND MJ FITTINGS SHALL BE ASTM 316.
- B) BE LOCATED ABOVE GROUND IN THE HEATED AND INSULATED ENCLOSURE SUCH AS HOTBOX MOUNTED ON MIN 6" THICK REINFORCED CONCRETE BASE.

VAULT NOTES:


- 1) TRAFFIC RATED LID
- 2) OPEN BOTTOM UNLESS IN HIGH GROUNDWATER AREAS, SEE SITE NOTE
- 3) EXCAVATION, BEDDING, BACKFILL & SURFACE RESTORATION TO BE DONE BY CONTRACTOR PER L&I REGULATIONS
- 4) 3/4" MIN CONDUIT REQUIRED FOR REMOTE READER, VAULT TO BUILDING OR BOLLARD (36" ABOVE GROUND), ETC
- 5) VAULT SIZE PER Y-115

APPROVED BY

 ENGINEERING SERVICES DIRECTOR KYLE TWOHIG
 CITY ENGINEER DAN BULLER, P.E.

ADOPTED: _____
 REVISED: 04/2021
 SUPERSEDES: 07/2020
 CHECKED BY: DCS
 SCALE: NTS
 DWG/REV. BY: ABM/MLD

IRRIGATION SERVICE WITH DCVA
 3"-6"
 ENGINEERING SERVICES
 CITY OF SPOKANE, WASHINGTON
 STANDARD
 PLAN No.
 Y-119





SITE NOTES:

IN SHALLOW GROUNDWATER AREAS WHERE SEASONAL HIGH LEVEL WILL REACH BOTTOM OF VAULT OR IS <7' DEEP, METER VAULT SHALL BE ONE OF THE FOLLOWING:

- BUOYANT RESISTANT VAULT WITH WATERTIGHT JOINTS AND PIPE PENETRATIONS, AND EXTERIOR WATER PROOF COATING (XYPEX OR EQUIVALENT). MIN 12" WIDE BY 6" DEEP SUMP TO BE PROVIDED FOR PUMP OUT. BOLTS FOR FLANGES AND MJ FITTINGS SHALL BE ASTM 316.
- BE LOCATED ABOVE GROUND IN THE HEATED AND INSULATED ENCLOSURE SUCH AS HOTBOX MOUNTED ON MIN 6" THICK REINFORCED CONCRETE BASE.

VAULT NOTES:

- TRAFFIC RATED LID
- OPEN BOTTOM UNLESS IN HIGH GROUNDWATER AREA, SEE SITE NOTE
- DIMENSIONS BASED ON: WILKINS 350A NEPTUNE HP PROTECTUS III METER
- EXCAVATION, BEDDING, BACKFILL & RESTORATION TO BE DONE BY CONTRACTOR PER L&I REGULATIONS.
- 3/4" MIN CONDUIT REQUIRED, STUB 36" ABOVE GROUND
- VAULT SIZE PER Y-115

<p>APPROVED BY</p>  <p>ENGINEERING SERVICES DIRECTOR KYLE TWOHIG</p> <p>CITY ENGINEER DAN BULLER, P.E.</p>	<p>ADOPTED: _____</p> <p>REVISED: 04/2021</p> <p>SUPERSEDES: 07/2020</p> <p>CHECKED BY: DCS</p> <p>SCALE: NTS</p> <p>DWG/REV. BY: ABM/MLD</p>	<p>DOMESTIC/FIRE LINE 4"-6", 8" OR 10"</p> <p>SERVICE REDUCED PRESSURE ASSEMBLY</p> <p>(PER WAC 246.290.490)</p> <p> ENGINEERING SERVICES</p> <p>CITY OF SPOKANE, WASHINGTON</p> <p>STANDARD PLAN No. Y-120</p>
---	---	---