



# RIVERFRONT PARK BRIDGES

## INSPECTION AND ANALYSIS

### NORTH SUSPENSION BRIDGE

NOVEMBER 14, 2014 | Final Report

# **NORTH SUSPENSION BRIDGE**

**November 14, 2014**

---

## **Prepared for**

**City of Spokane**

Steve Hansen, Senior Engineer

---

## **Prepared by**

**Kpff Consulting Engineers**

Marijean Frymoyer, PE

Project Engineer / Inspection Team Leader

---

## **Sub-consultants**

SWCA Environmental Consultant

Eileen Heideman

Architectural Historian

---

## **Table of Contents**

### **Bridge Inspection and Analysis Report**

1. Bridge Description
2. Document Review
3. Evaluation Procedures
4. Evaluation Findings
5. Conclusions and Recommendations
6. Permits and Cultural Resource Requirements

### **Appendix A**

Bridge Inspection Form

Key Photographs

Bridge Component Labeling System

### **Appendix B**

Bridge Improvement Details

Cost Estimate

### **Appendix C**

Load Rating Results & Calculations

### **Appendix D**

Photograph Log

Photograph Contact Sheet

# 1. BRIDGE DESCRIPTION

The north suspension pedestrian bridge was built for the 1974 Expo to carry pedestrians and bikes across the north channel of the Spokane River in Riverfront Park. The single-span North Suspension Bridge is 295 feet in length from tower to tower. The bridge superstructure is supported by hanger cables vertically connected to the main cables which are suspended from the towers. The floor system consists of weathering-steel edge girders, a concrete deck, horizontal bracing and a floor-beam that supports 15 electrical conduits running below the deck between vaults. The deck consists of reinforced concrete with stay-in-place (SIP) steel forms. Large hollow vaults that encompass the lower portion of each tower below the deck level have a ceiling/ cover that serve as an approach span. This span is constructed from concrete filled stay-in-place deck.



Figure 1: Aerial view of the Suspension Bridges (© 2012 Google Inc.)

## 2. DOCUMENT REVIEW

In preparation for this evaluation, Kpff reviewed the following documents related to the North Suspension Bridge:

- Structural design drawings (Plan no. G9-G15)
- Previous routine inspection reports
- Ultrasonic testing report (2009)
- Vault inspection report (2011)

## 3. EVALUATION PROCEDURES

### ROUTINE BRIDGE INSPECTION

The bridge was closed to pedestrian traffic for the duration of the bridge inspection. The maintenance department at Riverfront Park provided closure signs.

A visual inspection of the top of the deck, railings, and cable anchorages was performed. These components were accessed by foot. The curb and deck were sounded with a rock hammer to identify areas of delaminations. A visual inspection of the steel framing system, hanger cable bolt connections, and the bottom of the deck (SIP forms) was performed. These components were accessed by a climbing system anchored to the hanger cable connection above the curb and a back-up safety line anchored to the metal railing. The girder flanges and webs were measured with a D-meter and/or calipers at locations which showed evidence of section loss. A hands-on visual inspection of the main suspension cable connections at the towers, spreader bars and adjacent suspender cables was performed. These components were accessed by ascending a rope anchored to the spreader bars. The remainder of the hanger cables and the main suspension cables were also inspected. These cables were accessed with a 32-foot extension ladder (provided by the Riverfront Park maintenance department). A visual inspection of the vaults at the concrete towers was accessed by an extension ladder (provided by Avista). The vaults are considered a confined space; air monitoring equipment was provided by Avista.

### STRUCTURAL ANALYSIS

The main suspension cables, hanger cables, and steel girders were load rated using the LRFR method. The analysis was performed using CSiBridge. A uniform pedestrian live load of 90 psf and two vehicle live loads (6-foot-7-inch wheelbase/16,200 pounds and 8-foot-3-inch wheelbase/21,190 pounds) were used in the analysis. The vehicle weight distribution was assumed to be 75 percent of the total weight at the front axle and 25 percent of the total weight at the rear axle. The analysis assumed that there was only one vehicle on the bridge at a time and the vehicle load did not act concurrently with the uniform pedestrian live load. No impact was included for the live loads.

## 4. EVALUATION FINDINGS

### BRIDGE INSPECTION

The elements with the heaviest corrosion and overall deterioration are the deck, floor-beams, hanger cable bolts, and conduit roller supports. The construction joints in the deck allow water to penetrate through the top. The water is trapped in the SIP forms until it eventually rusts through. The water leaking through the deck and corroded SIP form eventually causes corrosion of the floorbeams and the conduit supports. Many of the horizontal plates connecting the lateral bracing to the girders are filled with debris, which traps moisture and causes the connections to corrode.

The metal railing, main suspension cable, hanger cables, steel pins, concrete towers, and cable anchorages are all in good condition. The steel girders are, overall, in satisfactory condition, with the exception of a few isolated areas that have moderate corrosion.

The concrete anchor blocks at the northwest and southeast ends of the bridge are buried. There is soil around the northeast and southwest anchors. The lock nut at the southwest anchor is only 30 percent engaged.



The SIP forms and steel supports in the vaults are severely corroded. The heaviest corrosion occurs at the locations where water can penetrate from the top of the deck. This includes areas around the manhole, around the concrete tower, and at the expansion joint at the bridge abutments. A large section of the SIP formwork is no longer in place adjacent to both bridge abutments.

The bridge inspection report, element numbering system, and photographs are included in Appendix A.

## **STRUCTURAL ANALYSIS**

The load rating analysis is reported as a Rating Factor (RF). The RF is the ratio of available capacity in each primary superstructure component over the specified live load combination under investigation. Based on AASHTO specifications, a RF less than 1.0 is interpreted to mean that one or more of the superstructure components do not meet current minimal capacity code standards and consideration should be given to either strengthening the subject component(s), or posting a sign identifying a maximum allowable load for the structure linked to the actual RF of the structure. Rating factors greater than 1.0 are interpreted to mean that all of the superstructure components have sufficient capacity to safely support the load under investigation, per the AASHTO specifications.

The minimum rating factor under the pedestrian live load, excluding the deck, is 1.08. The associated controlling component is the axial strength of the backstay anchorage cable. The minimum rating factor under the inspection vehicle live load is 1.45. The associated controlling component is the girder in flexure.

An analysis of the deck based on its current existing condition was also performed. In the original design of the deck the SIP forms were designed as a permanent structural member. Since the SIP place forms are heavily corroded in many locations, they were ignored for determining the capacity of the deck. The deck was analyzed assuming the average moment demands between a fix-fix and pin-pin connection between the slab and girders. The capacity of the deck is based on the tensile strength of the concrete. This analysis resulted in a RF = 0.51 for the deck in flexure under pedestrian loads. A load rating for the deck under vehicle loads was not performed, since vehicles are not currently allowed on the bridge.

The load rating calculations are included in Appendix C.

## **5. CONCLUSIONS AND RECOMMENDATIONS**

The North Suspension bridge structural condition, minus the deck, can be characterized as very good to fair - depending on which part of the bridge is being viewed. In General, the area above the deck including the tower is very good and the areas below the deck are satisfactory to fair. The steel area below the deck will be further investigated and upgraded as needed under our recommendations. Upon completion of this rehabilitation work the area both above and below the deck can be considered to be in good to very good condition. Some minor defects will remain but they will be immaterial to the inherent structural functioning capacity of the bridge as a whole.

In general, structural steel components that support bridges are conducive to corrosion from environmental conditions such as water, moisture, salts, air pollution, dirt and plants, bird droppings and bird nests. The more these items are kept away the longer the bridge will last. Maintenance is critical, especially in the form of cleaning and removing debris, bird nests and droppings from anyplace on the structure they can or do collect. The

Suspension bridges structural components while experiencing all degrees of corrosion (minor to severe) over the past 30 years has really overall performed fairly well.

Currently, there is no reason to suspect that this bridge will not be in service for at least another 50 years if repaired as recommended below, bi-annually inspected and maintained (cleaned) on an annual basis.

The steel used for this bridge is weathering steel. Its protective coat is a result of a thin film of rust. It is an excellent system for this environment. However, if over time this protection system appears to degrade, painting the bridge becomes an option which can easily buy another 20 to 30 years of service life for those components. Currently we are recommending painting for those areas already exposed to at least moderate levels of corrosion – generally around the panel point connections.

The deck is in poor to critical condition and must be replaced. A new, properly designed and constructed, deck should function well for another 30 to 50 years. It is recommended that salt not be applied ever to the new deck. It is far better to close the bridge if it seems the slippery to walk on with snow and ice. Salt leads to deterioration of concrete, the deck SIP forms, and any part of the steel components it touches.

Overall, the suspension bridges and vaults require a substantial amount of rehabilitation work to preserve their lifespan. The details of the bridge and vault improvement plans are included in Appendix B, along with a detailed cost estimate. The combined total cost for the recommended repairs for the North and South Suspension Bridges and Vaults is \$2.8 million.

Our recommendations to improve the bridge are summarized below.

## **DECK**

Due to the heavy corrosion of the SIP forms and the numerous areas of delaminations in the concrete, the deck and curb should be replaced. The new deck should have an improved drainage system to prevent future corrosion of the superstructure. A drainage channel could be added along the curb. The deck should receive a waterproofing sealant.

## **STEEL FRAMING SYSTEM**

The steel framing should be cleaned of debris and flaking steel. After the deck is removed and the steel is cleaned, another inspection should be performed to determine if there are areas of section loss that need to be reinforced. Floorbeams that are moderately to heavily corroded should be replaced. Floorbeams with minor corrosion should be cleaned and painted.

## **METAL RAILING**

The hand rail screws that have been stripped between hangers H1-H2 RT and H6-H7 RT should be replaced.

The clear opening between the railing posts does not meet current code. Consideration should be given to modifying the railing to meet code when the deck is replaced.

## **HANGER CABLE ANCHOR BOLTS**

The load rating analysis determined that the original anchor bolts had much more capacity than required based on the design loads. Therefore, if the anchor bolts only have a small to moderate amount of corrosion (less than 25% section loss), they will still have well above sufficient capacity to support dead and live loads. These anchor bolts should be cleaned of all rust and painted. Anchor bolts with severe corrosion (more than 25% section loss) should be replaced.

## **ELECTRICAL CONDUITS**

The conduit supports at the floorbeams are heavily corroded. The conduits are corroded in many locations. The conduits will need to be removed in order to clean and replace the floorbeams. The estimated cost and improvement details assume that all of the conduits and supports will be replaced.

## **CABLE ANCHORAGE**

The tree branches at the northwest anchorage should be cut back away from the cable. Expose the concrete anchorage blocks and remove the soil around the threaded rods. The lock nut should be tack welded into position at the southwest anchorage.

## **VAULTS AT CONCRETE TOWERS**

The deck and the steel framing in the vaults should be replaced and additional framing around the manhole opening should be provided. The conduits should be removed during construction, and the new deck should be constructed with removable formwork. The sidewalk around the vaults should also be replaced. A compression seal should be installed at the expansion joints to prevent the large intrusion of water at the joint.

## **FUTURE INSPECTIONS**

A routine walk-through inspection should be performed every two years. Kpff has provided inspection forms, which if utilized on a continual basis will, over time, provide an invaluable record of the bridge condition, areas of continual problems, and help inform the best way to care for the bridge and preserve the City's investment in its infrastructure.

# **6. PERMITS AND CULTURAL RESOURCE REQUIREMENTS**

## **PERMITS**

An environmental permit matrix was prepared by SWCA Environmental Consultants for the Riverfront Park Bridges. The proposed bridge improvement work may require the following permits or approvals:

- Hydraulic Project Approval permit from the Washington Department of Fish and Wildlife
- Critical Areas Review from the City of Spokane
- Shoreline Substantial Development Permit from the City of Spokane

More information can be found in SWCA's report.

# APPENDIX A

|                              | <u>PAGE</u> |
|------------------------------|-------------|
| BRIDGE INSPECTION FORM ..... | A-1         |

## LIST OF PHOTOGRAPHS

| <u>PHOTO</u> | <u>DESCRIPTION</u>   | <u>PAGE</u> |
|--------------|--|-------------|
| 1            | North Suspension Bridge Deck (Looking North) .....                               | A-3         |
| 2            | North Suspension Bridge Elevation (Looking West) .....                           | A-3         |
| 3            | Exposed Rebar in Deck .....  | A-4         |
| 4            | Loose Cover Plate on Handrail .....  | A-4         |
| 5            | Severe Corrosion/Flaking of Floorbeam 1-13 .....                                 | A-5         |
| 6            | Moderate Corrosion Bottom Flange of Left Girder at H5 .....                      | A-5         |
| 7            | Debris at Panel Point (Typical) .....  | A-6         |
| 8            | Typical Suspender Cable Connection .....   | A-6         |
| 9            | Hanger H10 LT, Broken Cotter Pin .....   | A-7         |
| 10           | Moderate to Heavy Corrosion at Interior Suspender Cable Connection (H5 RT) ..... | A-7         |
| 11           | Shrubs around Cable/Threaded Rod, Partially Buried Concrete Block .....          | A-8         |
| 12           | Lock Nut at Southwest Anchorage is only 30% Engaged .....                        | A-8         |
| 13           | Corroded/Missing Stay-in-Place Formwork above Floorbeam (Typical) .....          | A-9         |
| 14           | Corroded/Missing Stay-in-Place Formwork and Corroded Beam/Angle .....            | A-9         |
| 15           | Corroded Stay-in-Place Formwork around Manhole .....                             | A-9         |

|                                     | <u>PAGE</u> |
|-------------------------------------|-------------|
| BRIDGE COMPONENT LABELING SYSTEM:   |             |
| SUSPENDER CABLE / PANEL POINT ..... | A-10        |
| :                                   |             |
| FLOORBEAM .....                     | A-11        |
| BRIDGE COMPONENT LABELING SYSTEM:   |             |
| SPREADER BARS .....                 | A-11        |



# CITY OF SPOKANE

## PEDESTRIAN BRIDGE INSPECTION FORM

|                       |  |                       |  |                 |  |         |  |
|-----------------------|--|-----------------------|--|-----------------|--|---------|--|
|                       |  |                       |  | Bridge No.      |  |         |  |
| Bridge Name           |  |                       |  | Bridge Location |  |         |  |
| Inspection Date       |  | Inspector(s)          |  | Agency          |  |         |  |
| Access Method         |  |                       |  | Weather         |  |         |  |
| Load Rating Date      |  | Live Load             |  | Pedestrian      |  | Vehicle |  |
| Load Rating Factor(s) |  | Controlling Component |  | Pedestrian      |  | Vehicle |  |
|                       |  |                       |  |                 |  |         |  |

### Description of Bridge

### Summary of Condition and Critical Findings

### Summary of Recommendations

### Summary of Bridge Condition

| Bridge Component |  | No. of Compon. | % of ** | Condition Rating* |               |               | Comments |
|------------------|--|----------------|---------|-------------------|---------------|---------------|----------|
|                  |  |                |         | 8 – 7<br>Good     | 6 – 5<br>Fair | 4 – 3<br>Poor |          |
| 1                |  |                |         |                   |               |               |          |
| 2                |  |                |         |                   |               |               |          |
| 3                |  |                |         |                   |               |               |          |
| 4                |  |                |         |                   |               |               |          |
| 5                |  |                |         |                   |               |               |          |
| 6                |  |                |         |                   |               |               |          |
| 7                |  |                |         |                   |               |               |          |
| 8                |  |                |         |                   |               |               |          |
| 9                |  |                |         |                   |               |               |          |
| 10               |  |                |         |                   |               |               |          |
| 11               |  |                |         |                   |               |               |          |
| 12               |  |                |         |                   |               |               |          |
| 13               |  |                |         |                   |               |               |          |

\*See Page 2 for detailed descriptions    \*\*Condition rating percentages are based on the % of area, length, or each of the bridge components inspected.

### GENERAL NOTES

| DESCRIPTION OF CONDITION OF BRIDGE COMPONENT  |                 |   |
|---|-----------------|---|
| Condition Value   | Material        | Description   |
| <b>8 – 7</b><br>Very good → Good<br>2 yr. insp. Cycle<br>No repairs.  | Steel           | Like new, surface rust, minor pitting, no material loss. Connections are good. No damage.   |
|   | Concrete        | No to minor/ insignificant defects includes: cracks, spalls, chips, consolidation, efflorescence.   |
|   | Timber          | Beams: Minor splits, checks, or defects (one side), no decay or insects – sounds solid.<br>Posts: Splits or cracks less than 3/8" (one side), no decay or insects – sounds solid.   |
|   | Paint           | No defects, no sign of rust including no freckled rust, no peeling, no exposed steel.   |
|   | Scour / Erosion | None or minor.  |
| <b>6 – 5</b><br>Satisfactory → Fair<br>1 – 2 yr insp. cycle<br>Monitor for repairs<br>Paint: Max 10 year life estimate      | Steel           | Moderate corrosion, pitting, flaking, pack rust. Material loss is evident but barely measurable. Connections have up to moderate corrosion but remain fully functional. No cracks.  |
|   | Concrete        | Some spalling but exposed rebar (if any) is insignificant or exhibits some surface rust; delamination is evident with or without evidence of rebar corrosion. Shear zone cracks are tight, barely measureable, and low density. Flexure zone cracks are measurable but less than .035 inch and low density. Concrete may exhibit: efflorescence (moderate to heavy), surface rust, heavy map cracking, very poor consolidation. Settlement cracks in foundations and wall are stable and less than 1/4" wide. |
|   | Timber          | Beams: Less than 3/8" splits – two sides or greater than 3/8" on one side. Some decay (max 10% by volume), some softness but sounds solid – no insects.<br>Posts: More than 1/2 "splits – two sides or greater than 3/4" on one side. Decay is evident (greater than 20% by volume), timber may have extensive wetness and softness.  |
|   | Paint           | Freckled rust, small areas of exposed steel, some peeling, oxidized.  |
|   | Scour / Erosion | Evidence of scour, exposed footing, no undermining. Banks are sloughing, protection, if any, needs repair.  |
| <b>4 – 3</b><br>Poor → Critical<br>3 mo – 1 yr. insp. cycle (as needed)<br>Repairs needed. (ASAP or one year)<br>Re - paint | Steel           | Heavy to severe: corrosion, pitting, pack rust. Measurable material loss. Connections are heavily corroded, missing, and questionable functionality. Fatigue cracks.  |
|   | Concrete        | Large spalls, deep w/ exposed and corroded rebar w/ material loss evident. Cracks are wider, closely spaced, clearly structural in nature both in shear and flexure zone. Concrete quality appears poor w/ heavy scaling, stagilites, efflorescence, map cracking, extensive surface rust and delamination, and very poor consolidation of concrete. Settlement cracks are significant.   |
|   | Timber          | Beams: Greater than 3/8" on two sides. Moderate decay up to 20%, surface softness, do not sound solid – may have insects.<br>Posts: Less than 1/2 "splits – two sides or greater than 1/2" on one side. Decay is evident (20%), wetness and soft.   |
|   | Paint           | Extensive freckled rust, larger areas of exposed steel, heavily oxidized, extensive peeling.  |
|   | Scour / Erosion | Undermining or threatens undermining in a manner that could impact structure stability. Banks are heavily eroded, protection if any is non-functional.  |

#### Additional Comments by Component Number

| Bridge Comp. No. | Comments |
|------------------|----------|
|                  |          |
|                  |          |
|                  |          |
|                  |          |
|                  |          |
|                  |          |
|                  |          |
|                  |          |



Photo 1 –North Suspension Bridge Deck (Looking North)



Photo 2 – North Suspension Bridge Elevation (Looking West)





Photo 3 – Exposed Rebar in Deck




Photo 4 – Loose Cover Plate on Handrail



Photo 5 – Moderate Corrosion/Flaking of Floorbeam 1-13



Photo 6 –Moderate Corrosion Bottom Flange of Left Girder at H5





Photo 7 – Debris at Panel Point (Typical)



Photo 8 – Typical Suspender Cable Connection




Photo 9 – Hanger H10 LT, Broken Cotter Pin



Photo 10 – Moderate to Heavy Corrosion at Interior Suspender Cable Connection (H5 RT)





Photo 11 – Shrubs around Cable/Threaded Rod, Partially Buried Concrete Block



Photo 12 – Lock Nut at Southwest Anchorage is only 30% Engaged







Photo 13 – Corroded/Missing Stay-in-Place Formwork above Floorbeam (Typical)



Photo 14 – Corroded/Missing Stay-in-Place Formwork and Corroded Beam/Angle in Vault No. 3 near Abutment





Photo 15 – Corroded Stay-in-Place Formwork around Manhole





\*Designate Left (LT) or Right (RT) Hanger

Bridge Component Labeling System: Suspender Cable / Panel Point





Bridge Component Labelling System: Floorbeam



Bridge Component Labelling System: Spreader Bar

# APPENDIX B

## BRIDGE IMPROVEMENT DETAILS COST ESTIMATES



- \*\* EXISTING ANCHOR BOLTS WITH EQUAL OR LESS THAN 25% SECTION LOSS SHALL BE CLEANED AND PAINTED.


[illegible]

|                                 |   |  |          |
|---------------------------------|---|--|----------|
| NAVDSB - (1025 DWM 122) 1-11-13 |   | AS OF JANUARY, 2020 USE NORTH AMERICAN VERTICAL DATUM OF 1986 (NAVDSB) |          |
| BENCH MARK LOCATION             |   | CURRENT C.O.S. DRAFTING STANDARDS ADOPTED FEB. 2007                    |          |
| NAVDSB ELEV. -                  | BAR IS ONE INCH ON ORIGINAL DRAWING.                      | HORIZONTAL PLANE PROFILE   | AS SHOWN |
| CDM NO. -                       | IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY. | VERTICAL PROFILE ONLY  |          |
| NAVDSB DATUM                    |   | SCALE  |          |
|                                 |   | DRAWN BY   | DATE     |
|                                 |   | REVISED MLF  | 1/1/14   |
|                                 |   | CHECKED TW   | 1/1/14   |
|                                 |   | APPROVED MLF   | 1/1/14   |




CITY OF SPOKANE, WASHINGTON  
DEPARTMENT OF ENGINEERING SERVICES  
808 WEST SPOKANE FALLS BLVD.  
SPOKANE, WASHINGTON 99201-3343  
(509) 625-6700


|                                  |  |                         |             |
|----------------------------------|--|-------------------------|-------------|
| PROJECT NAME                     |  | RIVERFRONT PARK BRIDGES |             |
| BRIDGE NAME                      |  | TYPE OF IMPROVEMENT     | BRIDGE      |
| NORTH & SOUTH SUSPENSION BRIDGES |  | CITY PROJECT NUMBER     | PLAN NUMBER |
| DECK REPLACEMENT & REHAB         |  | 2013186                 |             |
| TYPICAL SECTION                  |  | EPN. ...                | 1 of 3      |




**VAULT #1 – PLAN REMOVAL**  
SCALE: 3/8"=1'-0"



**VAULT #1 – PLAN REPLACEMENT**  
SCALE: 3/8"=1'-0"




**SECTION A – REMOVAL**  
SCALE: 3/8"=1'-0"



**SECTION B – REPLACEMENT**  
SCALE: 3/8"=1'-0"

Name: Tautel Date: Nov 11, 2014 11:47:45am File: V:\114176 (Spokane River Front Bridges)\Suspension Bridge\Design\SB-S02.dwg

|  |    |  |             |                             |    |                                    |             |                              |    |                                |             |                |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
|--|----|--|-------------|-----------------------------|----|------------------------------------|-------------|------------------------------|----|--------------------------------|-------------|----------------|----|----------------------|-------------|--------------|--|------|----|-------|-------------|------|----|-------|-------------|------|----|-------|-------------|------|----|-------|-------------|--|--|--|--|--|--|--|--|--|--|-------------------------------------|--|--|--|---------------------|--|---|--|-------------|--|---|--|---------|--|---|--|------|--|---|--|----------|--|---|--|--|--|--|--|--|--|--|--|--|--|---|--|-----------------|--|-----------------------------|--|------------------------------------|--|------------------------------|--|--------------------------------|--|----------------|--|-----------|--|--------|--|----|--|-------|--|--------|--|--------|--|--------|--|--------------|--|--------|--|-------------|--|--------|--|---------------|--|--------|--|--------|--|--|--|--|--|--|--|--|--|--|--|---------------|--|-------------------------|--|--------------|--|----------------------------------|--|----------------------|--|---------|--|------------------|--|--------|--|
| <table><tr><td colspan="2">REVISIONS</td><td colspan="2">AS BUILT</td><td colspan="2">GRADE ORDINANCE LIST</td><td colspan="2">NAVD88 DATUM</td></tr><tr><td>DATE</td><td>BY</td><td>PROJ.</td><td>DESCRIPTION</td><td>DATE</td><td>BY</td><td>PROJ.</td><td>DESCRIPTION</td><td>DATE</td><td>BY</td><td>PROJ.</td><td>DESCRIPTION</td><td>DATE</td><td>BY</td><td>PROJ.</td><td>DESCRIPTION</td></tr></table> |    |  |             |                             |    |                                    |             |                              |    | REVISIONS                      |             | AS BUILT       |    | GRADE ORDINANCE LIST |             | NAVD88 DATUM |  | DATE | BY | PROJ. | DESCRIPTION | DATE | BY | PROJ. | DESCRIPTION | DATE | BY | PROJ. | DESCRIPTION | DATE | BY | PROJ. | DESCRIPTION | <table><tr><td colspan="2">NAVDS - (ADD CBM ELEV.) - (11.1.13)</td><td colspan="2">AS OF JANUARY, 2000 USE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)</td></tr><tr><td colspan="2">BENCH MARK LOCATION</td><td colspan="2">-</td></tr><tr><td colspan="2">NAVDS ELEV.</td><td colspan="2">-</td></tr><tr><td colspan="2">CBM NO.</td><td colspan="2">-</td></tr><tr><td colspan="2">DATE</td><td colspan="2">-</td></tr><tr><td colspan="2">FILE NO.</td><td colspan="2">-</td></tr></table> |  |  |  |  |  |  |  |  |  | NAVDS - (ADD CBM ELEV.) - (11.1.13) |  | AS OF JANUARY, 2000 USE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88) |  | BENCH MARK LOCATION |  | - |  | NAVDS ELEV. |  | - |  | CBM NO. |  | - |  | DATE |  | - |  | FILE NO. |  | - |  | <table><tr><td colspan="2">CURRENT C.O.S. DRAFTING STANDARDS ADOPTED FEB. 2007</td><td colspan="2">CITY OF SPOKANE</td><td colspan="2">CITY OF SPOKANE, WASHINGTON</td><td colspan="2">DEPARTMENT OF ENGINEERING SERVICES</td><td colspan="2">808 WEST SPOKANE FALLS BLVD.</td><td colspan="2">SPOKANE, WASHINGTON 99201-3343</td><td colspan="2">(509) 625-6700</td></tr><tr><td colspan="2">DRAWN: HT</td><td colspan="2">1/1/14</td><td colspan="2">BY</td><td colspan="2">DATES</td><td colspan="2">1/1/14</td><td colspan="2">1/1/14</td><td colspan="2">1/1/14</td></tr><tr><td colspan="2">REVISED: MLF</td><td colspan="2">1/1/14</td><td colspan="2">CHECKED: TW</td><td colspan="2">1/1/14</td><td colspan="2">APPROVED: MLF</td><td colspan="2">1/1/14</td><td colspan="2">1/1/14</td></tr></table> |  |  |  |  |  |  |  |  |  | CURRENT C.O.S. DRAFTING STANDARDS ADOPTED FEB. 2007 |  | CITY OF SPOKANE |  | CITY OF SPOKANE, WASHINGTON |  | DEPARTMENT OF ENGINEERING SERVICES |  | 808 WEST SPOKANE FALLS BLVD. |  | SPOKANE, WASHINGTON 99201-3343 |  | (509) 625-6700 |  | DRAWN: HT |  | 1/1/14 |  | BY |  | DATES |  | 1/1/14 |  | 1/1/14 |  | 1/1/14 |  | REVISED: MLF |  | 1/1/14 |  | CHECKED: TW |  | 1/1/14 |  | APPROVED: MLF |  | 1/1/14 |  | 1/1/14 |  | <table><tr><td colspan="2">PROJECT NAME:</td><td colspan="2">RIVERFRONT PARK BRIDGES</td></tr><tr><td colspan="2">BRIDGE NAME:</td><td colspan="2">NORTH &amp; SOUTH SUSPENSION BRIDGES</td></tr><tr><td colspan="2">CITY PROJECT NUMBER:</td><td colspan="2">2013186</td></tr><tr><td colspan="2">PLAN AND SECTION</td><td colspan="2">2 of 3</td></tr></table> |  |  |  |  |  |  |  |  |  | PROJECT NAME: |  | RIVERFRONT PARK BRIDGES |  | BRIDGE NAME: |  | NORTH & SOUTH SUSPENSION BRIDGES |  | CITY PROJECT NUMBER: |  | 2013186 |  | PLAN AND SECTION |  | 2 of 3 |  |
| REVISIONS  |    | AS BUILT   |             | GRADE ORDINANCE LIST        |    | NAVD88 DATUM                       |             |                              |    |                                |             |                |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| DATE   | BY | PROJ.  | DESCRIPTION | DATE                        | BY | PROJ.                              | DESCRIPTION | DATE                         | BY | PROJ.                          | DESCRIPTION | DATE           | BY | PROJ.                | DESCRIPTION |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| NAVDS - (ADD CBM ELEV.) - (11.1.13)  |    | AS OF JANUARY, 2000 USE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88) |             |                             |    |                                    |             |                              |    |                                |             |                |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| BENCH MARK LOCATION  |    | -  |             |                             |    |                                    |             |                              |    |                                |             |                |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| NAVDS ELEV.  |    | -  |             |                             |    |                                    |             |                              |    |                                |             |                |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| CBM NO.  |    | -  |             |                             |    |                                    |             |                              |    |                                |             |                |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| DATE   |    | -  |             |                             |    |                                    |             |                              |    |                                |             |                |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| FILE NO.   |    | -  |             |                             |    |                                    |             |                              |    |                                |             |                |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| CURRENT C.O.S. DRAFTING STANDARDS ADOPTED FEB. 2007  |    | CITY OF SPOKANE  |             | CITY OF SPOKANE, WASHINGTON |    | DEPARTMENT OF ENGINEERING SERVICES |             | 808 WEST SPOKANE FALLS BLVD. |    | SPOKANE, WASHINGTON 99201-3343 |             | (509) 625-6700 |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| DRAWN: HT  |    | 1/1/14   |             | BY                          |    | DATES                              |             | 1/1/14                       |    | 1/1/14                         |             | 1/1/14         |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| REVISED: MLF   |    | 1/1/14   |             | CHECKED: TW                 |    | 1/1/14                             |             | APPROVED: MLF                |    | 1/1/14                         |             | 1/1/14         |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| PROJECT NAME:  |    | RIVERFRONT PARK BRIDGES  |             |                             |    |                                    |             |                              |    |                                |             |                |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| BRIDGE NAME:   |    | NORTH & SOUTH SUSPENSION BRIDGES                                       |             |                             |    |                                    |             |                              |    |                                |             |                |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| CITY PROJECT NUMBER:   |    | 2013186  |             |                             |    |                                    |             |                              |    |                                |             |                |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |
| PLAN AND SECTION   |    | 2 of 3   |             |                             |    |                                    |             |                              |    |                                |             |                |    |                      |             |              |  |      |    |       |             |      |    |       |             |      |    |       |             |      |    |       |             |  |  |  |  |  |  |  |  |  |  |                                     |  |  |  |                     |  |   |  |             |  |   |  |         |  |   |  |      |  |   |  |          |  |   |  |  |  |  |  |  |  |  |  |  |  |   |  |                 |  |                             |  |                                    |  |                              |  |                                |  |                |  |           |  |        |  |    |  |       |  |        |  |        |  |        |  |              |  |        |  |             |  |        |  |               |  |        |  |        |  |  |  |  |  |  |  |  |  |  |  |               |  |                         |  |              |  |                                  |  |                      |  |         |  |                  |  |        |  |



CALL BEFORE YOU DIG 1-800-424-5555

## Cost Estimates for Bridge Improvements Based on the 2014 KPFF Inspection and Analysis Recommendations

**Bridge Name:** Two Suspension Bridges (North and South) and Vault decks.  
**Combined Bridge Length and Width (feet)** 474 10

**Recommendations for Improvements - Include:** Deck Replacement, Structural Steel Improvements,  
 Vault Rehabilitation

| Item no  | Item Description                              | Cost Unit | Quantity | Unit Cost | Item Cost           |
|--|---|-----------|----------|-----------|---------------------|
| 1  | Existing Rail Remove and Re-install           | LF        | 474      | 90        | \$ 42,660           |
| 2  | Replace Existing Anchor Bolts                 | EA        | 25       | 1250      | \$ 31,000           |
| 3  | Clean and Paint In-situ Anchor Bolts          | EA        | 223      | 450       | \$ 100,440          |
| 4  | Remove Existing Deck and Curb                 | SF        | 4740     | 45        | \$ 213,300          |
| 5  | New Deck and Curb                             | SF        | 4740     | 65        | \$ 308,100          |
| 6  | Replace Floorbeams                            | EA        | 9        | 4500      | \$ 38,925           |
| 7  | Clean, Strengthen, & Paint in-situ Floorbeams | EA        | 26       | 1500      | \$ 39,525           |
| 8  | Replace Conduits and Supports                 | LF        | 7110     | 12        | \$ 85,320           |
| 9  | Edge Girder Repair and Painting               | LF        | 948      | 250       | \$ 237,000          |
| 10   | Repair/Replace Vault Deck and Adj. Sidewalk   | EA        | 4        | 25000     | \$ 100,000          |
| 12   | Misc and Constructibility Access              | LS        | 2        | 100000    | \$ 200,000          |
| Total  |   |           |          |           | \$ 1,396,270        |
| 13   | Mobilization                                  | 12%       |          |           | \$ 167,552          |
| 14   | Design, Permits, Survey                       | 30%       |          |           | \$ 418,881          |
| 15   | Construction Management                       | 13%       |          |           | \$ 174,534          |
| 16   | Taxes   | 8%        |          |           | \$ 111,702          |
| 17   | Contingency                                   | 30%       |          |           | \$ 418,881          |
| 18   | Excalation (1 year)                           | 3%        |          |           | \$ 41,888           |
| 19   | Agency Project Development & Mngmt.           | 5%        |          |           | \$ 69,814           |
| Total  |   |           |          |           | \$ 1,403,251        |
| <b>Total Project Cost (2015)</b>               |   |           |          |           | <b>\$ 2,799,521</b> |
| Square Foot Cost - includes Vault Area (\$/SF) |   |           |          |           | \$ 545              |

Note: Total project cost is for both north and south suspension bridges and all four vault repairs.

# APPENDIX C

## LOAD RATING RESULTS AND CALCULATIONS



## Structural Analysis – Load Rating Summary

### LRFR Bridge Rating Summary

#### Strength I – Rating Factors (RF):

|                   | Pedestrian                    |             | Vehicle                       |             |
|-------------------|-------------------------------|-------------|-------------------------------|-------------|
|                   | Inventory                     | Operating   | Inventory                     | Operating   |
| Deck (Stress) RF  | <b>0.51</b>                   | <b>0.66</b> | N/A                           | N/A         |
| Controlling Point | Center of Deck                |             | N/A                           |             |
| Steel (Moment) RF | 3.30                          | 4.28        | <b>1.45</b>                   | <b>1.88</b> |
| Controlling Point | Girders at Hanger Connections |             | Girders at Hanger Connections |             |
| Cable (Axial) RF  | 1.08                          | 1.40        | 7.38                          | 9.57        |
| Controlling Point | Backstay Cables               |             | Backstay Cables               |             |
| Pylon (M+A) RF    | 1.73                          | 2.24        | 12.8                          | 16.6        |
| Controlling Point | Base of Pylon                 |             | Base of Pylon                 |             |

#### Maximum Pedestrian Live Load

Inventory =  $0.51 \times 90 \text{ psf} = 46 \text{ psf}$

Operating =  $0.66 \times 90 \text{ psf} = 59 \text{ psf}$

Pedestrian = 90 psf uniform distributed load

Vehicle = Bridge Inspection Vehicles

(12,150 lb. front axle, 4,050 lb. rear axle, 6'-7" axle spacing)

(15,895 lb. front axle, 5,300 lb. rear axle, 8'-3" axle spacing)

Weights provided by City of Spokane Engineering Department

Figures C3.1-1 and C3.1-2 from the *LRFD Guide Specifications for the Design of Pedestrian Bridges* (December 2009) give a visual representation of the uniform pedestrian live load.



Figure C3.1-1—Live Load of 50 psf



Figure C3.1-2—Live Load of 100 psf

**Structural Analysis - Load Rating**

## Design Parameters:

*Concrete* $f'_c = 4,000 \text{ psi @ 28 days}$ Rebar –  $f_y = 60,000 \text{ psi}$ *Steel*Yield Stress,  $f_y = 50 \text{ ksi}$ Modulus of Elasticity,  $E = 29,000 \text{ ksi}$ *Cables*Yield Stress,  $f_y = 160 \text{ ksi}$ Tensile Stress,  $f_u = 200 \text{ ksi}$ Modulus of Elasticity,  $E = 20,000 \text{ ksi}$ *Dead Loads*

Superstructure self weight

Curb and railing

Conduits

(CSiBridge Load – Sched3-ZERO, step 31)

*Live Loads*

Pedestrian Uniform Load = 90 psf

(CSiBridge Load – Pedestrian)

Vehicle Load = 16,200 lb inspection vehicle

(CSiBridge Load – Truck 1)

Vehicle Load = 21,190 lb inspection vehicle

(CSiBridge Load – Truck 2)

Impact is not included

Pedestrian and Vehicle Loads do not act concurrently


## Analysis Methods:

The bridge geometry, section properties, and cables were modeled in CSiBridge based on the “As Built” drawings. The force in the cables was not specified so they were set to values that resulted in zero dead load deflection. The moment, shear, and axial demands due to dead loads and live loads were exported from CSiBridge to Excel. The moment, shear, and axial capacities were calculated in Excel. The Strength I rating factors were calculated in Excel using the peak demands in each element type.


The visual bridge inspection completed on September 5, 2014 found the deck to be in poor condition, and the floor beams to be in fair condition. All other superstructure components were shown to be in good condition. The condition rating factor,  $\phi_c$ , is equal to 1.0 for good members, 0.95 for fair members, and 0.85 for poor members. The system rating factor,  $\phi_s$  is equal to 1.0 for redundant members such as the deck, floorbeams, crossbracing, and spreader bars, and 0.85 for all other non redundant members.

The Strength I Load Rating checks flexure, shear, and axial capacities, as well as combined concurrent moment and axial capacity. Each member was checked individually and compared to the demands given in the CSiBridge model. The deck was not load rated for vehicles as it is in poor condition and is being recommended for replacement. No vehicles shall be allowed on the existing deck.


## North Suspension Bridge Undeformed




## North Suspension Bridge Extruded View



## North Suspension Bridge Dead Load Moment




## North Suspension Bridge Dead Load Shear






## North Suspension Bridge Pedestrian Axial Force



## North Suspension Bridge Vehicular Moment



## North Suspension Bridge Load Rating (LRFR Method)

### Concrete Deck

|                   |                          |
|-------------------|--------------------------|
| $t_{middle}$      | 5 in                     |
| $t_{edges}$       | 4 in                     |
| $h_{corregation}$ | 1.5 in                   |
| $t_{average}$     | 3.75 in                  |
| clear cov.        | 1.5 in                   |
| $d_{trans. bars}$ | 1.75 in                  |
| $A_{bars}$        | 0.2 in <sup>2</sup>      |
| $S_{bars}$        | 9 in                     |
| $f_y$             | 60 ksi                   |
| $w_{deck}$        | 8.79 ft                  |
| $S$               | 28.1 in <sup>3</sup> /ft |
| $f'_c$            | 4 ksi                    |
| $\gamma_c$        | 0.16 kcf                 |
| $\beta_1$         | 0.85                     |

*\*Conservatively neglect corrugated metal formwork and strength of concrete in corregation. Since the transverse steel is so high up in the section, check the bending stress in the bottom of the slab at the middle instead of the moment. The deck is assumed to be between fixed-fixed and pinned-pinned at the curbs. Curbs not checked.*

### Dead Loads

Self Weight of deck is only dead load

|                    |   |              |
|--------------------|---|--------------|
| <b>Weight</b>      | $W_{deck} = t_{average} * \gamma_c * 1 \text{ ft} =$    | 50.0 lb/ft   |
| <b>Moment</b>      | $M_{deck \text{ fixed}} = W_{deck} * b_{deck}^2 / 24 =$ | 161 lb-ft/ft |
|                    | $M_{deck \text{ pinned}} = W_{deck} * b_{deck}^2 / 8 =$ | 483 lb-ft/ft |
| <b>Bot. Stress</b> | $\sigma_{deck} = M_{deck \text{ avg.}} / S =$           | 137 psi      |
| <b>Shear</b>       | $V_{deck} = W_{deck} * b_{deck} / 2 =$                  | 220 lb/ft    |

### Live Loads

Pedestrian and Vehicular loads act separately

|                           |   |              |                            |
|---------------------------|---|--------------|----------------------------|
| <u><b>Pedestrian:</b></u> | PL  | 90 psf       | AASHTO LRFD Ped Bridge 3.1 |
| <b>Weight</b>             | $W_{PL} = PL * 1 \text{ ft} =$                        | 90 lb/ft     |                            |
| <b>Moment</b>             | $M_{deck \text{ fixed}} = W_{PL} * b_{deck}^2 / 24 =$ | 290 lb-ft/ft |                            |
|                           | $M_{deck \text{ pinned}} = W_{PL} * b_{deck}^2 / 8 =$ | 870 lb-ft/ft |                            |
| <b>Bot. Stress</b>        | $\sigma_{PL} = M_{PL \text{ avg.}} / S =$             | 247 psi      |                            |
| <b>Shear</b>              | $V_{PL} = W_{PL} * b_{deck} / 2 =$                    | 396 lb/ft    |                            |

|                          |               |         |          |  |
|--------------------------|---------------|---------|----------|--|
| <u><b>Vehicular:</b></u> | LL            | Truck 1 | Truck 2  |  |
| <b>Weight</b>            | Total         | 16.2    | 21.19 k  |  |
|                          | Axle 1 Wheels | 6.08    | 7.95 k   |  |
|                          | Axle 2 Wheels | 2.03    | 2.65 k   |  |
|                          | wheel spacing | 6       | 6 ft     |  |
|                          | axle spacing  | 6.58    | 8.25 ft  |  |
| <b>Moment</b>            | $M_{LL} =$    | N/A     | lb-ft/ft | Vehicular demands not checked as vehicles are not allowed on bridge. |
| <b>Shear</b>             | $V_{LL} =$    | N/A     | lb/ft    |  |

## Capacity

### Shear

$$V_n = V_c + V_s$$

AASHTO 5.8.3.3-1

$$\Phi = 0.9$$

AASHTO 5.5.4.2

$$V_c = 0.0316 \cdot \beta \cdot v(f'_c) \cdot b_v d_v$$

AASHTO 5.8.3.3-3

$$\beta = 2$$

AASHTO 5.8.3.4.1

$$b_v = 12 \text{ in} \quad (\text{Unit width})$$

$$d_v = M_n / (A_s f_y) < \min(0.9d, 0.72h)$$

AASHTO 5.8.2.9

$$d_v = 1.80 \text{ in}$$

$$V_c = 2730 \text{ lb/ft}$$

$$V_s = 0 \quad (\text{Conservative assumption})$$

$$\Phi V_n = 2730 \text{ lb/ft}$$

### Direct Concrete Tensile Strength

$$f_r = 0.23 \cdot v f'_c = 0.46 \text{ ksi}$$

AASHTO C5.4.2.7

## Rating Factors

$$RF = \frac{(C - V_{DC}DC - V_{DW}DW + / - V_P P)}{V_{LL}LL(1+IM)}$$

AASHTO MBE 6A.4.2.1-1

$$C_{Str-I} = \Phi_c \Phi_s \Phi_n R_n$$

AASHTO MBE 6A.4.2.1-2

$$\Phi_c \Phi_s \geq 0.85$$

AASHTO MBE 6A.4.2.1-3

$$\Phi_s = 1$$

AASHTO MBE 6A.4.2.4

$$V_{DC} = 1.25$$

$$V_{LL \text{ inv.}} = 1.75$$

$$V_{LL \text{ op.}} = 1.35$$

$$IM = 0$$

AASHTO LRFD Ped. Bridge Manual 3.2

Bottom Stress

|           | Condition            | Good        | Fair        | Poor        |
|-----------|----------------------|-------------|-------------|-------------|
|           | $\Phi_c$             | 1           | 0.95        | 0.85        |
|           | C [psi]              | 460         | 437         | 391         |
| <b>RF</b> | pedestrian inventory | <b>0.67</b> | <b>0.61</b> | <b>0.51</b> |
| <b>RF</b> | pedestrian operating | <b>0.86</b> | <b>0.79</b> | <b>0.66</b> |
| <b>RF</b> | vehicle inventory    | <b>N/A</b>  | <b>N/A</b>  | <b>N/A</b>  |
| <b>RF</b> | vehicle operating    | <b>N/A</b>  | <b>N/A</b>  | <b>N/A</b>  |

Shear

|           | Condition            | Good        | Fair        | Poor        |
|-----------|----------------------|-------------|-------------|-------------|
|           | $\Phi_c$             | 1           | 0.95        | 0.85        |
|           | C [lb/ft]            | 2730        | 2594        | 2321        |
| <b>RF</b> | pedestrian inventory | <b>3.55</b> | <b>3.35</b> | <b>2.96</b> |
| <b>RF</b> | pedestrian operating | <b>4.60</b> | <b>4.34</b> | <b>3.83</b> |
| <b>RF</b> | vehicle inventory    | <b>N/A</b>  | <b>N/A</b>  | <b>N/A</b>  |
| <b>RF</b> | vehicle operating    | <b>N/A</b>  | <b>N/A</b>  | <b>N/A</b>  |

## North Suspension Bridge Load Rating (LRFR Method)

### Girders

|                   |                      |                      |           |
|-------------------|----------------------|----------------------|-----------|
| L                 | 268 ft               |                      |           |
| Spacing           | 9.5 ft               |                      |           |
| Crossbeam Spacing | 15.25 ft             |                      |           |
| Size              | W18x50               |                      |           |
| $b_f$             | 7.50 in              | $F_{yc}$             | 50 ksi    |
| $t_f$             | 0.570 in             | $F_{yw}$             | 50 ksi    |
| $r_t$             | 1.98 in              | $F_{yr} = 0.7F_{yc}$ | 35 ksi    |
| d                 | 18 in                | E                    | 29000 ksi |
| D                 | 16.9 in              |                      |           |
| $t_w$             | 0.355 in             |                      |           |
| $S_x$             | 88.9 in <sup>3</sup> |                      |           |

### **Dead Loads**

|               |           |     |            |                        |
|---------------|-----------|-----|------------|------------------------|
| <i>Moment</i> | $M_{max}$ | (+) | 87.6 k-in  |                        |
|               | $M_{min}$ | (-) | 202.4 k-in | (from CSiBridge Model) |
| <i>Shear</i>  | $V_{max}$ |     | 2.48 k     |                        |

### **Live Loads**

Pedestrian and Vehicular loads act separately

|                    |                           |        |                            |
|--------------------|---------------------------|--------|----------------------------|
| <u>Pedestrian:</u> | PL                        | 90 psf | AASHTO LRFD Ped Bridge 3.1 |
| <i>Weight</i>      | $W_{PL} = PL * w_{trib.}$ | =      | 427.5 plf                  |

|               |           |     |            |                        |
|---------------|-----------|-----|------------|------------------------|
| <i>Moment</i> | $M_{max}$ | (+) | 431.2 k-in |                        |
|               | $M_{min}$ | (-) | 226.0 k-in | (from CSiBridge Model) |
| <i>Shear</i>  | $V_{max}$ |     | 2.15 k     |                        |

|                   |               |         |         |
|-------------------|---------------|---------|---------|
| <u>Vehicular:</u> | LL            | Truck 1 | Truck 2 |
| <i>Weight</i>     | Total         | 16.2    | 21.19 k |
|                   | Axle 1 Wheels | 6.08    | 7.95 k  |
|                   | Axle 2 Wheels | 2.03    | 2.65 k  |
|                   | wheel spacing | 6       | 6 ft    |
|                   | axle spacing  | 6.58    | 8.25 ft |

|               |           |     |            |  |
|---------------|-----------|-----|------------|--|
| <i>Moment</i> | $M_{max}$ | (+) | 1016 k-in  |  |
|               | $M_{min}$ | (-) | 305.0 k-in | (From CSiBridge Model, Truck 2 controls) |
| <i>Shear</i>  | $V_{max}$ |     | 7.47 k     |  |

**Capacity**

Local Buckling Resistance

|  |        |  |
|--|--------|--|
|  |        | AASHTO 6.10.8.2.2                                    |
| $\lambda_f = b_{fc}/2t_{fc} =$                                     | 6.58   | AASHTO 6.10.8.2.2-3                                  |
| $\lambda_{pf} = 0.38*\sqrt{E/F_{yc}} =$                            | 9.15   | AASHTO 6.10.8.2.2-4                                  |
| $\lambda_{rf} = 0.56*\sqrt{E/F_{yr}} =$                            | 13.49  | AASHTO 6.10.8.2.2-5                                  |
| $\lambda_f < \lambda_{pf} \rightarrow F_{nc} = R_b * R_h * F_{yc}$ |        | AASHTO 6.10.8.2.2-1                                  |
| $R_b$  | 1      | AASHTO 6.10.1.10.2                                   |
| $R_h$  | 1      | AASHTO 6.10.1.10.1 (constructability is not checked) |
| $F_{nc} =$   | 50 ksi |  |

Lateral Torsional Buckling

|   |                   |   |
|---|-------------------|---|
|   |                   | AASHTO 6.10.8.2.3                       |
| $L_b$   | 15.25 ft          |   |
| $L_p = r_t * \sqrt{E/F_{yc}} =$                                 | 3.97 ft           | AASHTO 6.10.8.2.3-4                     |
| $L_r = \pi * r_t * \sqrt{E/F_{yr}} =$                           | 14.92 ft          | AASHTO 6.10.8.2.3-5                     |
| $L_b > L_r \rightarrow F_{nc} = F_{cr} \leq R_b * R_h * F_{yc}$ |                   |   |
| $F_{cr} = \frac{C_b * R_h * \pi^2 * E}{(L_b/r_t)^2}$            |                   | AASHTO 6.10.8.2.3-9                     |
| $C_b = 1.75 - 1.05(M_1/M_2) + 0.3(M_1/M_2)^2 \leq 2.3$          |                   | AASHTO 6.10.8.2.3-7                     |
|   | (-M) (+M)         |   |
| $M_{2(veh.)} =$   | -305.0 1016 k-in  | largest moment at end of braced length  |
| $M_{mid(veh.)} =$   | -269.5 760 k-in   | moment at middle of braced length       |
| $M_{0(veh.)} =$   | -234.1 504 k-in   | smallest moment at end of braced length |
| $M_{1(veh.)} = M_{0(veh.)} =$                                   | -234.1 504 k-in   | AASHTO A6.3.3-12                        |
| $C_b(veh.) =$   | 1.12 1.30         |   |
|   | (-M) (+M)         |   |
| $M_{2(ped.)} =$   | -226.0 431.2 k-in | largest moment at end of braced length  |
| $M_{mid(ped.)} =$   | -31.2 407.1 k-in  | moment at middle of braced length       |
| $M_{0(ped.)} =$   | 163.7 383.1 k-in  | smallest moment at end of braced length |
| $M_{1(ped.)} = M_{0(ped.)} =$                                   | 163.7 383.1 k-in  | AASHTO A6.3.3-12                        |
| $C_b(ped.) =$   | 2.30 1.03         |   |
|   | (-M) (+M)         |   |
| $F_{cr(veh.)} =$  | 37.6 43.7 ksi     |   |
| $F_{cr(ped.)} =$  | 77.1 34.4 ksi     |   |
| $F_{nc(veh. \& -ped)} =$  | 37.6 ksi          |   |
| $F_{nc+ped} =$  | 34.4 ksi          |   |



Tension Flange Flexural Resistance

$$F_{nt} = R_h * F_{yt} = 50 \text{ ksi} \quad \text{AASHTO 6.10.8.3-1}$$

Minimum Flexural Resistance

$$\Phi M_{n33} = \Phi_f * S_x * \min(F_{nc}, F_{nt})$$

$$\Phi_f = 1 \quad \text{AASHTO 6.5.4.2}$$

$$\Phi M_{n \text{ veh. \& -ped}} = 3339 \text{ k-in}$$

$$\Phi M_{n \text{ +ped}} = 3061 \text{ k-in}$$

Unstiffened Web Shear Resistance

AASHTO 6.10.9.2

$$\Phi V_n = \Phi_v V_{cr} = \Phi_v C V_p$$

$$\Phi_v = 1 \quad \text{AASHTO 6.5.4.2}$$

$$V_p = 0.58 * F_{yw} * D * t_w = 173.6 \text{ k} \quad \text{AASHTO 6.10.9.2-2}$$

$$D/t_w = 47.5$$

$$k = 5$$

$$1.12 * \sqrt{E * k / F_{yw}} = 60.3$$

$$\text{if } D/t_w < 1.12 * \sqrt{E * k / F_{yw}} \rightarrow C=1$$

$$C = 1$$

$$\Phi V_n = 173.6 \text{ k}$$

**Rating Factors**

$$RF_{\text{general}} = \frac{(C - \gamma_{DC} DC - \gamma_{DW} DW + / - \gamma_P P)}{\gamma_{LL} LL (1+IM)} \quad \begin{array}{l} \text{AASHTO MBE 6A.4.2.1-1} \\ \text{(Impact for vehicles only)} \end{array}$$

$$C_{\text{Str-I}} = \Phi_c \Phi_s \Phi_n R_n \quad \text{AASHTO MBE 6A.4.2.1-2}$$

$$\Phi_c \Phi_s \geq 0.85 \quad \text{AASHTO MBE 6A.4.2.1-3}$$

$$\Phi_s = 0.85 \quad \text{AASHTO MBE 6A.4.2.4}$$

$$\gamma_{DC} = 1.25$$

$$\gamma_{LL \text{ inv.}} = 1.75$$

$$\gamma_{LL \text{ op.}} = 1.35$$

$$IM = 0 \quad \text{AASHTO LRFD Ped. Bridge Manual 3.2}$$

**Flexure**

| Condition                                | Good        | Fair        | Poor        |
|--|-------------|-------------|-------------|
| $\Phi_c$                                 | 1           | 0.95        | 0.85        |
| C [k-in]                                 | 2602        | 2602        | 2602        |
| <b>RF<sub>pedestrian inventory</sub></b> | <b>3.30</b> | <b>3.30</b> | <b>3.30</b> |
| <b>RF<sub>pedestrian operating</sub></b> | <b>4.28</b> | <b>4.28</b> | <b>4.28</b> |
| C [k-in]                                 | 2838        | 2838        | 2838        |
| <b>RF<sub>vehicle inventory</sub></b>    | <b>1.45</b> | <b>1.45</b> | <b>1.45</b> |
| <b>RF<sub>vehicle operating</sub></b>    | <b>1.88</b> | <b>1.88</b> | <b>1.88</b> |

**Shear**

| Condition                                | Good        | Fair        | Poor        |
|--|-------------|-------------|-------------|
| $\Phi_c$                                 | 1           | 0.95        | 0.85        |
| C [k]                                    | 148         | 148         | 148         |
| <b>RF<sub>pedestrian inventory</sub></b> | <b>38.5</b> | <b>38.5</b> | <b>38.5</b> |
| <b>RF<sub>pedestrian operating</sub></b> | <b>49.9</b> | <b>49.9</b> | <b>49.9</b> |
| <b>RF<sub>vehicle inventory</sub></b>    | <b>11.0</b> | <b>11.0</b> | <b>11.0</b> |
| <b>RF<sub>vehicle operating</sub></b>    | <b>14.3</b> | <b>14.3</b> | <b>14.3</b> |

## North Suspension Bridge Load Rating (LRFR Method)

### Floorbeams

|         |                      |                      |           |
|---------|----------------------|----------------------|-----------|
| L       | 9.5 ft               |                      |           |
| Spacing | 15.25 ft             |                      |           |
| Size    | W6x20                |                      |           |
| $b_f$   | 6.08 in              | $F_{yc}$             | 50 ksi    |
| $t_f$   | 0.37 in              | $F_{yw}$             | 50 ksi    |
| $r_t$   | 1.70 in              | $F_{yr} = 0.7F_{yc}$ | 35 ksi    |
| $d$     | 6.2 in               | E                    | 29000 ksi |
| $D$     | 5.47 in              |                      |           |
| $t_w$   | 0.26 in              |                      |           |
| $S_x$   | 13.4 in <sup>3</sup> |                      |           |

### Dead Loads

|        |           |            |                        |
|--------|-----------|------------|------------------------|
| Moment | $M_{max}$ | 14.83 k-in | (from CSiBridge Model) |
| Shear  | $V_{max}$ | 0.86 k     |                        |

### Live Loads

Pedestrian and Vehicular loads act separately

|                    |                                 |           |                                |
|--------------------|---------------------------------|-----------|--------------------------------|
| <u>Pedestrian:</u> | PL                              | 90 psf    | AASHTO LRFD Ped Bridge 3.1     |
| Weight             | $P_{PL} = PL \cdot A_{trib.} =$ | 13.0 k    | (two point loads of this mag.) |
| Moment             | $M_{max}$                       | 5.19 k-in |                                |
| Shear              | $V_{max}$                       | 0.01 k    | (from CSiBridge Model)         |

|                   |               |         |         |
|-------------------|---------------|---------|---------|
| <u>Vehicular:</u> | LL            | Truck 1 | Truck 2 |
| Total             |               | 16.2    | 21.19 k |
| Weight            | Axle 1 Wheels | 6.08    | 7.95 k  |
|                   | Axle 2 Wheels | 2.03    | 2.65 k  |
|                   | wheel spacing | 6       | 6 ft    |
|                   | axle spacing  | 6.58    | 8.25 ft |

|        |           |            |  |
|--------|-----------|------------|--|
| Moment | $M_{max}$ | 12.24 k-in | (From CSiBridge Model, Truck 2 controls) |
| Shear  | $V_{max}$ | 0.09 k     |  |

### Capacity

|   |       |                     |
|---|-------|---------------------|
| <u>Local Buckling Resistance</u>              |       | AASHTO 6.10.8.2.2   |
| $\lambda_f = b_{fc}/2t_{fc} =$                | 8.33  | AASHTO 6.10.8.2.2-3 |
| $\lambda_{pf} = 0.38 \cdot \sqrt{E/F_{yc}} =$ | 9.15  | AASHTO 6.10.8.2.2-4 |
| $\lambda_{rf} = 0.56 \cdot \sqrt{E/F_{yr}} =$ | 13.49 | AASHTO 6.10.8.2.2-5 |

$$\lambda_f < \lambda_{pf} \rightarrow F_{nc} = R_b \cdot R_h \cdot F_{yc}$$

AASHTO 6.10.8.2.2-1

$$R_b = 1$$

AASHTO 6.10.1.10.2

$$R_h = 1$$

AASHTO 6.10.1.10.1 (constructability is not checked)

$$F_{nc} = 50 \text{ ksi}$$

Lateral Torsional Buckling

AASHTO 6.10.8.2.3

$$L_b = 9.5 \text{ ft}$$

$$L_p = r_t \cdot \sqrt{E/F_{yc}} = 3.41 \text{ ft}$$

AASHTO 6.10.8.2.3-4

$$L_r = \pi \cdot r_t \cdot \sqrt{E/F_{yr}} = 12.81 \text{ ft}$$

AASHTO 6.10.8.2.3-5

$$L_p < L_b < L_r \rightarrow F_{nc} = C_b [1 - (1 - F_{yr}/(R_h F_{yc}))((L_b - L_p)/(L_r - L_p))] R_b R_h F_{yc} < R_b R_h F_{yc}$$

$$C_b = 1.75 - 1.05(M_1/M_2) + 0.3(M_1/M_2)^2 \leq 2.3$$

AASHTO 6.10.8.2.3-7

$$M_{2(\text{veh.})} = 12.2 \text{ k-in}$$

largest moment at end of braced length

$$M_{\text{mid}(\text{veh.})} = 10.7 \text{ k-in}$$

moment at middle of braced length

$$M_{0(\text{veh.})} = 9.3 \text{ k-in}$$

smallest moment at end of braced length

$$M_{1(\text{veh.})} = M_{0(\text{veh.})} = 9.3 \text{ k-in}$$

AASHTO A6.3.3-12

$$C_b(\text{vehicle}) = 1.13$$

$$M_{2(\text{ped.})} = 5.2 \text{ k-in}$$

largest moment at end of braced length

$$M_{\text{mid}(\text{ped.})} = 4.8 \text{ k-in}$$

moment at middle of braced length

$$M_{0(\text{ped.})} = 4.5 \text{ k-in}$$

smallest moment at end of braced length

$$M_{1(\text{ped.})} = M_{0(\text{ped.})} = 4.5 \text{ k-in}$$

AASHTO A6.3.3-12

$$C_b(\text{ped.}) = 1.03$$

$$F_{nc(\text{veh.})} = 45.4 \text{ ksi}$$

$$F_{nc(\text{ped.})} = 41.7 \text{ ksi}$$

Tension Flange Flexural Resistance

$$F_{nt} = R_h \cdot F_{yt} = 50 \text{ ksi}$$

AASHTO 6.10.8.3-1

Minimum Flexural Resistance

$$\Phi M_n = \Phi_f \cdot S_x \cdot \min(F_{nc}, F_{nt})$$

$$\Phi_f = 1$$

AASHTO 6.5.4.2

$$\Phi M_n = 558 \text{ k-in}$$

Unstiffened Web Shear Resistance

AASHTO 6.10.9.2

$$\Phi V_n = \Phi_v V_{cr} = \Phi_v C V_p$$

$$\Phi_v = 1$$

AASHTO 6.5.4.2

$$V_p = 0.58 * F_{yw} * D * t_w = 41.2 \text{ k} \quad \text{AASHTO 6.10.9.2-2}$$

$$D/t_w = 21.0$$

$$k = 5$$

$$1.12 * \sqrt{E * k / F_{yw}} = 60.3$$

$$\text{if } D/t_w < 1.12 * \sqrt{E * k / F_{yw}} \rightarrow C=1$$

$$C = 1$$

$$\Phi V_n = 41.2 \text{ k}$$

### Rating Factors

$$RF = \frac{(C - V_{DC}DC - V_{DW}DW + / - V_P P)}{V_{LL}LL(1+IM)} \quad \text{AASHTO MBE 6A.4.2.1-1}$$

$$C_{Str-I} = \Phi_c \Phi_s \Phi_n R_n \quad \text{AASHTO MBE 6A.4.2.1-2}$$

$$\Phi_c \Phi_s \geq 0.85 \quad \text{AASHTO MBE 6A.4.2.1-3}$$

$$\Phi_s = 1 \quad \text{AASHTO MBE 6A.4.2.4}$$

$$V_{DC} = 1.25$$

$$V_{LL \text{ inv.}} = 1.75$$

$$V_{LL \text{ op.}} = 1.35$$

$$IM = 0 \quad \text{AASHTO LRFD Ped. Bridge Manual 3.2}$$

### Flexure

| Condition                                 | Good        | Fair        | Poor        |
|---|-------------|-------------|-------------|
| $\Phi_c$                                  | 1           | 0.95        | 0.85        |
| C [k-in]                                  | 558         | 530         | 475         |
| <b>RF</b> <sub>pedestrian inventory</sub> | <b>59.5</b> | <b>56.4</b> | <b>50.3</b> |
| <b>RF</b> <sub>pedestrian operating</sub> | <b>77.1</b> | <b>73.1</b> | <b>65.1</b> |
| <b>RF</b> <sub>vehicle inventory</sub>    | <b>25.2</b> | <b>23.9</b> | <b>21.3</b> |
| <b>RF</b> <sub>vehicle operating</sub>    | <b>32.7</b> | <b>31.0</b> | <b>27.6</b> |

Shear

| Condition                                 | Good        | Fair        | Poor        |
|---|-------------|-------------|-------------|
| $\Phi_c$                                  | 1           | 0.95        | 0.85        |
| C [k]                                     | 41.2        | 39.2        | 35.1        |
| <b>RF</b> <sub>pedestrian inventory</sub> | <b>1000</b> | <b>1000</b> | <b>1000</b> |
| <b>RF</b> <sub>pedestrian operating</sub> | <b>1000</b> | <b>1000</b> | <b>1000</b> |
| <b>RF</b> <sub>vehicle inventory</sub>    | <b>255</b>  | <b>242</b>  | <b>216</b>  |
| <b>RF</b> <sub>vehicle operating</sub>    | <b>331</b>  | <b>314</b>  | <b>280</b>  |

## North Suspension Bridge Load Rating (LRFR Method)

### Crossbracing

|                |                             |                                     |                  |  |
|----------------|-----------------------------|-------------------------------------|------------------|--|
| L              | 18 <i>ft</i>                |                                     |                  |  |
| Size           | W6x15                       |                                     |                  |  |
| b <sub>f</sub> | 5.99 <i>in</i>              | F <sub>yc</sub>                     | 50 <i>ksi</i>    |  |
| t <sub>f</sub> | 0.26 <i>in</i>              | F <sub>yw</sub>                     | 50 <i>ksi</i>    |  |
| r <sub>t</sub> | 1.66 <i>in</i>              | F <sub>yr</sub> =0.7F <sub>yc</sub> | 35 <i>ksi</i>    |  |
| d              | 5.99 <i>in</i>              | E                                   | 29000 <i>ksi</i> |  |
| D              | 5.47 <i>in</i>              |                                     |                  |  |
| t <sub>w</sub> | 0.23 <i>in</i>              |                                     |                  |  |
| S <sub>x</sub> | 29.1 <i>in</i> <sup>3</sup> |                                     |                  |  |

### Dead Loads

|        |           |            |                        |
|--------|-----------|------------|------------------------|
| Moment | $M_{max}$ | 11.85 k-in | (from CSiBridge Model) |
| Shear  | $V_{max}$ | 0.24 k     |                        |

### Live Loads

Pedestrian and Vehicular loads act separately

|                    |    |        |                            |
|--------------------|----|--------|----------------------------|
| <u>Pedestrian:</u> | PL | 90 psf | AASHTO LRFD Ped Bridge 3.1 |
|--------------------|----|--------|----------------------------|

|        |           |           |                        |
|--------|-----------|-----------|------------------------|
| Moment | $M_{max}$ | 14.6 k-in | (from CSiBridge Model) |
| Shear  | $V_{max}$ | 0.09 k    |                        |

|                   |               |         |         |
|-------------------|---------------|---------|---------|
| <u>Vehicular:</u> | LL            | Truck 1 | Truck 2 |
| Total             |               | 16.2    | 21.19 k |
| Weight            | Axle 1 Wheels | 6.08    | 7.95 k  |
|                   | Axle 2 Wheels | 2.03    | 2.65 k  |
|                   | wheel spacing | 6       | 6 ft    |
|                   | axle spacing  | 6.58    | 8.25 ft |

|        |           |           |  |
|--------|-----------|-----------|--|
| Moment | $M_{max}$ | 47.3 k-in | (From CSiBridge Model, Truck 2 controls) |
| Shear  | $V_{max}$ | 0.25 k    |  |

### Capacity

|  |       |                     |
|--|-------|---------------------|
| <u>Local Buckling Resistance</u>       |       | AASHTO 6.10.8.2.2   |
| $\lambda_f = b_{fc}/2t_{fc} =$         | 11.52 | AASHTO 6.10.8.2.2-3 |
| $\lambda_{pf} = 0.38\sqrt{E/F_{yc}} =$ | 9.15  | AASHTO 6.10.8.2.2-4 |
| $\lambda_{rf} = 0.56\sqrt{E/F_{yr}} =$ | 13.49 | AASHTO 6.10.8.2.2-5 |

$$\lambda_{pf} < \lambda_r < \lambda_{rf} \rightarrow F_{nc} = [1 - (1 - F_{yr}/R_h F_y)((\lambda_r - \lambda_{pf})/(\lambda_{rf} - \lambda_{pf}))] R_b R_h F_{yc} \quad \text{AASHTO 6.10.8.2.2-1}$$

$$R_b = 1 \quad \text{AASHTO 6.10.1.10.2}$$

$$R_h = 1 \quad \text{AASHTO 6.10.1.10.1 (constructability is not checked)}$$

$$F_{nc} = 41.8 \text{ ksi}$$

Lateral Torsional Buckling

AASHTO 6.10.8.2.3

$$L_b = 18 \text{ ft}$$

$$L_p = r_t \sqrt{E/F_{yc}} = 3.33 \text{ ft} \quad \text{AASHTO 6.10.8.2.3-4}$$

$$L_r = \pi r_t \sqrt{E/F_{yr}} = 12.51 \text{ ft} \quad \text{AASHTO 6.10.8.2.3-5}$$

$$L_b > L_r \rightarrow F_{nc} = F_{cr} < R_b R_h F_{yc}$$

$$F_{cr} = C_b R_b \pi^2 E / (L_b / r_t)^2$$

$$C_b = 1$$

$$F_{cr} = 16.9 \text{ ksi}$$

$$F_{nc} = 16.9 \text{ ksi}$$

Tension Flange Flexural Resistance

$$F_{nt} = R_h F_{yt} = 50 \text{ ksi} \quad \text{AASHTO 6.10.8.3-1}$$

Minimum Flexural Resistance

$$\Phi M_n = \Phi_f S_x \min(F_{nc}, F_{nt})$$

$$\Phi_f = 1 \quad \text{AASHTO 6.5.4.2}$$

$$\Phi M_n = 492 \text{ k-in}$$

Unstiffened Web Shear Resistance

AASHTO 6.10.9.2

$$\Phi V_n = \Phi_v V_{cr} = \Phi_v C V_p$$

$$\Phi_v = 1 \quad \text{AASHTO 6.5.4.2}$$

$$V_p = 0.58 F_{yw} D t_w = 36.5 \text{ k} \quad \text{AASHTO 6.10.9.2-2}$$

$$D/t_w = 23.8$$

$$k = 5$$

$$1.12 \sqrt{E k / F_{yw}} = 60.3$$

$$\text{if } D/t_w < 1.12 \sqrt{E k / F_{yw}} \rightarrow C=1$$

$$C = 1$$

$$\Phi V_n = 36.5 \text{ k}$$



## Rating Factors

$$RF = \frac{(C - V_{DC}DC - V_{DW}DW + / - V_P P)}{V_{LL}LL(1+IM)}$$

AASHTO MBE 6A.4.2.1-1

$$C_{Str-I} = \Phi_c \Phi_s \Phi_n R_n$$

$\Phi_c \Phi_s \geq 0.85$

$\Phi_s$  1

AASHTO MBE 6A.4.2.1-2  
AASHTO MBE 6A.4.2.1-3  
AASHTO MBE 6A.4.2.4

|                       |      |                                    |
|-----------------------|------|------------------------------------|
| $V_{DC}$              | 1.25 |                                    |
| $V_{LL \text{ inv.}}$ | 1.75 |                                    |
| $V_{LL \text{ op.}}$  | 1.35 |                                    |
| IM                    | 0    | AASHTO LRFD Ped. Bridge Manual 3.2 |

### Flexure

| Condition                                | Good        | Fair        | Poor        |
|--|-------------|-------------|-------------|
| $\Phi_c$                                 | 1           | 0.95        | 0.85        |
| C [k-in]                                 | 492         | 467         | 418         |
| <b>RF<sub>pedestrian inventory</sub></b> | <b>18.6</b> | <b>17.7</b> | <b>15.8</b> |
| <b>RF<sub>pedestrian operating</sub></b> | <b>24.2</b> | <b>22.9</b> | <b>20.4</b> |
| <b>RF<sub>vehicle inventory</sub></b>    | <b>5.76</b> | <b>5.47</b> | <b>4.87</b> |
| <b>RF<sub>vehicle operating</sub></b>    | <b>7.47</b> | <b>7.09</b> | <b>6.31</b> |

### Shear

| Condition                                | Good        | Fair        | Poor        |
|--|-------------|-------------|-------------|
| $\Phi_c$                                 | 1           | 0.95        | 0.85        |
| C [k]                                    | 36.5        | 34.7        | 31.0        |
| <b>RF<sub>pedestrian inventory</sub></b> | <b>230</b>  | <b>218</b>  | <b>195</b>  |
| <b>RF<sub>pedestrian operating</sub></b> | <b>298</b>  | <b>283</b>  | <b>253</b>  |
| <b>RF<sub>vehicle inventory</sub></b>    | <b>83.4</b> | <b>79.2</b> | <b>70.8</b> |
| <b>RF<sub>vehicle operating</sub></b>    | <b>108</b>  | <b>103</b>  | <b>91.7</b> |

## North Suspension Bridge Load Rating (LRFR Method)

### Hanger Cables

|                |                       |  |  |                                    |
|----------------|-----------------------|--|--|------------------------------------|
| Size           | $1\frac{11}{16}$ "    | (Structural Steel Strand ASTM - A586, Class A Coating) |  |                                    |
| $A_g$          | 0.284 in <sup>2</sup> |  |  |                                    |
| Breaking Force | 58 k                  |  |  | (from Bethlehem Wire Rope catalog) |
| E              | 24000 ksi             |  |  |                                    |

### Dead Loads

|       |           |        |                        |
|-------|-----------|--------|------------------------|
| Axial | $P_{max}$ | 8.85 k | (from CSiBridge Model) |
|-------|-----------|--------|------------------------|

### Live Loads

Pedestrian and Vehicular loads act separately

|                    |    |        |                            |
|--------------------|----|--------|----------------------------|
| <u>Pedestrian:</u> | PL | 90 psf | AASHTO LRFD Ped Bridge 3.1 |
|--------------------|----|--------|----------------------------|

|       |           |        |                        |
|-------|-----------|--------|------------------------|
| Axial | $P_{max}$ | 6.79 k | (from CSiBridge Model) |
|-------|-----------|--------|------------------------|

|                   |               |         |         |
|-------------------|---------------|---------|---------|
| <u>Vehicular:</u> | LL            | Truck 1 | Truck 2 |
|                   | Total         | 16.2    | 21.19 k |
| Weight            | Axle 1 Wheels | 6.08    | 7.95 k  |
|                   | Axle 2 Wheels | 2.03    | 2.65 k  |
|                   | wheel spacing | 6       | 6 ft    |
|                   | axle spacing  | 6.58    | 8.25 ft |

|       |           |        |  |
|-------|-----------|--------|--|
| Axial | $P_{max}$ | 1.65 k | (From CSiBridge Model, Truck 2 controls) |
|-------|-----------|--------|--|

### Capacity

#### Tensile Resistance

$$\Phi P_n = \Phi_u F_y A_n R_p U \quad \text{AASHTO 6.8.2.1-2}$$

$$\Phi_u = 0.8 \quad \text{AASHTO 6.5.4.2}$$

$$F_y A_n = \text{Breaking Force}$$

$$R_p = 1.0$$

$$U = 1.0$$

$$\Phi P_n = 46.4 \text{ k}$$

### Rating Factors

$$RF = \frac{(C - \gamma_{DC} DC - \gamma_{DW} DW + / - \gamma_P P)}{\gamma_{LL} LL(1+IM)} \quad \text{AASHTO MBE 6A.4.2.1-1}$$

$$C_{Str-I} = \Phi_c \Phi_s \Phi_n R_n \quad \text{AASHTO MBE 6A.4.2.1-2}$$

$$\Phi_c \Phi_s \geq 0.85 \quad \text{AASHTO MBE 6A.4.2.1-3}$$

$$\Phi_s = 0.85 \quad \text{AASHTO MBE 6A.4.2.4}$$

|                       |      |
|-----------------------|------|
| $V_{DC}$              | 1.25 |
| $V_{LL \text{ inv.}}$ | 1.75 |
| $V_{LL \text{ op.}}$  | 1.35 |
| IM                    | 0    |

AASHTO LRFD Ped. Bridge Manual 3.2

**Axial**

| Condition                                 | Good        | Fair        | Poor        |
|---|-------------|-------------|-------------|
| $\Phi_c$                                  | 1           | 0.95        | 0.85        |
| C [k]                                     | 39.4        | 39.4        | 39.4        |
| <b>RF</b> <sub>pedestrian inventory</sub> | <b>2.39</b> | <b>2.39</b> | <b>2.39</b> |
| <b>RF</b> <sub>pedestrian operating</sub> | <b>3.10</b> | <b>3.10</b> | <b>3.10</b> |
| <b>RF</b> <sub>vehicle inventory</sub>    | <b>9.83</b> | <b>9.83</b> | <b>9.83</b> |
| <b>RF</b> <sub>vehicle operating</sub>    | <b>12.7</b> | <b>12.7</b> | <b>12.7</b> |

## North Suspension Bridge Load Rating (LRFR Method)

### Main Cables

|                  |                      |  |
|------------------|----------------------|--|
| Size             | 2 7/8"               | (Structural Steel Rope - ASTM A603, Class A Coating) |
| $A_g$            | 3.91 in <sup>2</sup> |  |
| Nominal Strength | 758 k                | (from Bethlehem Wire Rope catalog)                   |
| E                | 20000 ksi            |  |

### Dead Loads

|       |           |         |                        |
|-------|-----------|---------|------------------------|
| Axial | $P_{max}$ | 177.3 k | (from CSiBridge Model) |
|-------|-----------|---------|------------------------|

### Live Loads

Pedestrian and Vehicular loads act separately

|                    |    |        |                            |
|--------------------|----|--------|----------------------------|
| <u>Pedestrian:</u> | PL | 90 psf | AASHTO LRFD Ped Bridge 3.1 |
|--------------------|----|--------|----------------------------|

|       |           |         |                        |
|-------|-----------|---------|------------------------|
| Axial | $P_{max}$ | 129.6 k | (from CSiBridge Model) |
|-------|-----------|---------|------------------------|

|                   |               |         |         |
|-------------------|---------------|---------|---------|
| <u>Vehicular:</u> | LL            | Truck 1 | Truck 2 |
|                   | Total         | 16.2    | 21.19 k |
| Weight            | Axle 1 Wheels | 6.08    | 7.95 k  |
|                   | Axle 2 Wheels | 2.03    | 2.65 k  |
|                   | wheel spacing | 6       | 6 ft    |
|                   | axle spacing  | 6.58    | 8.25 ft |

|       |           |        |  |
|-------|-----------|--------|--|
| Axial | $P_{max}$ | 19.1 k | (From CSiBridge Model, Truck 2 controls) |
|-------|-----------|--------|--|

### Capacity

#### Tensile Resistance

$$\Phi P_n = \Phi_u F_y A_n R_p U \quad \text{AASHTO 6.8.2.1-2}$$

$$\Phi_u = 0.8 \quad \text{AASHTO 6.5.4.2}$$

$$F_y A_n = \text{Breaking Force}$$

$$R_p = 1.0$$

$$U = 1.0$$

$$\Phi P_n = 606 \text{ k}$$

### Rating Factors

$$RF = \frac{(C - \gamma_{DC} DC - \gamma_{DW} DW + / - \gamma_P P)}{\gamma_{LL} LL(1+IM)} \quad \text{AASHTO MBE 6A.4.2.1-1}$$

$$C_{Str-I} = \Phi_c \Phi_s \Phi_n R_n \quad \text{AASHTO MBE 6A.4.2.1-2}$$

$$\Phi_c \Phi_s \geq 0.85 \quad \text{AASHTO MBE 6A.4.2.1-3}$$

$$\Phi_s = 0.85 \quad \text{AASHTO MBE 6A.4.2.4}$$

|                       |      |
|-----------------------|------|
| $V_{DC}$              | 1.25 |
| $V_{LL \text{ inv.}}$ | 1.75 |
| $V_{LL \text{ op.}}$  | 1.35 |
| IM                    | 0    |

AASHTO LRFD Ped. Bridge Manual 3.2

**Axial**

|   | Condition | Good        | Fair        | Poor        |
|---|-----------|-------------|-------------|-------------|
| $\Phi_c$                                  |           | 1           | 0.95        | 0.85        |
| C [k]                                     |           | 515         | 515         | 515         |
| <b>RF</b> <sub>pedestrian inventory</sub> |           | <b>1.30</b> | <b>1.30</b> | <b>1.30</b> |
| <b>RF</b> <sub>pedestrian operating</sub> |           | <b>1.68</b> | <b>1.68</b> | <b>1.68</b> |
| <b>RF</b> <sub>vehicle inventory</sub>    |           | <b>8.79</b> | <b>8.79</b> | <b>8.79</b> |
| <b>RF</b> <sub>vehicle operating</sub>    |           | <b>11.4</b> | <b>11.4</b> | <b>11.4</b> |

## North Suspension Bridge Load Rating (LRFR Method)

### Backstay Cables

|                  |                       |  |
|------------------|-----------------------|--|
| Size             | $d = 2 \frac{3}{4}''$ | (Structural Steel Strand ASTM - A586, Class A Coating) |
| $A_g$            | $4.54 \text{ in}^2$   |  |
| Nominal Strength | 904                   | k (from Bethlehem Wire Rope catalog)                   |
| E                | 23000                 | ksi  |

|                  |                       |  |
|------------------|-----------------------|--|
| Size             | $d = 2 \frac{5}{8}''$ | (Structural Steel Strand ASTM - A586, Class A Coating) |
| $A_g$            | $4.13 \text{ in}^2$   |  |
| Nominal Strength | 834                   | k (from Bethlehem Wire Rope catalog)                   |
| E                | 23000                 | ksi  |

|                   |            |                   |                   |                          |
|-------------------|------------|-------------------|-------------------|--------------------------|
| <b>Dead Loads</b> |            | $2 \frac{3}{4}''$ | $2 \frac{5}{8}''$ |                          |
| <i>Axial</i>      | $P_{\max}$ | 219.2             | 205.4             | k (from CSiBridge Model) |

### Live Loads

Pedestrian and Vehicular loads act separately

|                    |            |                   |                   |                            |
|--------------------|------------|-------------------|-------------------|----------------------------|
| <u>Pedestrian:</u> | PL         | 90                | psf               | AASHTO LRFD Ped Bridge 3.1 |
|                    |            | $2 \frac{3}{4}''$ | $2 \frac{5}{8}''$ |                            |
| <i>Axial</i>       | $P_{\max}$ | 155.5             | 145.8             | k (from CSiBridge Model)   |

|                   |               |         |         |
|-------------------|---------------|---------|---------|
| <u>Vehicular:</u> | LL            | Truck 1 | Truck 2 |
|                   | Total         | 16.2    | 21.19   |
| <i>Weight</i>     | Axle 1 Wheels | 6.08    | 7.95    |
|                   | Axle 2 Wheels | 2.03    | 2.65    |
|                   | wheel spacing | 6       | 6       |
|                   | axle spacing  | 6.58    | 8.25    |

|              |            |                   |                   |                                   |
|--------------|------------|-------------------|-------------------|-----------------------------------|
|              |            | $2 \frac{3}{4}''$ | $2 \frac{5}{8}''$ |                                   |
| <i>Axial</i> | $P_{\max}$ | 22.7              | 21.4              | k (from CSiBridge Model, Truck 2) |

### Capacity

#### Tensile Resistance

|                                   |                   |                   |
|-----------------------------------|-------------------|-------------------|
| $\Phi P_n = \Phi_u F_y A_n R_p U$ |                   | AASHTO 6.8.2.1-2  |
| $\Phi_u$                          | 0.8               | AASHTO 6.5.4.2    |
| $F_y A_n$                         | = Breaking Force  |                   |
| $R_p$                             | 1.0               |                   |
| U                                 | 1.0               |                   |
|                                   | $2 \frac{3}{4}''$ | $2 \frac{5}{8}''$ |
| $\Phi P_n =$                      | 723               | 667               |

## Rating Factors

$$RF = \frac{(C - V_{DC}DC - V_{DW}DW + / - V_P P)}{V_{LL}LL(1+IM)}$$

AASHTO MBE 6A.4.2.1-1

$$C_{Str-I} = \Phi_c \Phi_s \Phi_n R_n$$

$\Phi_c \Phi_s \geq 0.85$

$\Phi_s$  0.85

AASHTO MBE 6A.4.2.1-2  
AASHTO MBE 6A.4.2.1-3  
AASHTO MBE 6A.4.2.4

$$V_{DC} = 1.25$$

$$V_{LL \text{ inv.}} = 1.75$$

$$V_{LL \text{ op.}} = 1.35$$

$$IM = 0$$

AASHTO LRFD Ped. Bridge Manual 3.2

## Axial

|           |                             | $2 \frac{3}{4}"$ |             |             | $2 \frac{5}{8}"$ |             |             |
|-----------|-----------------------------|------------------|-------------|-------------|------------------|-------------|-------------|
|           | Condition                   | Good             | Fair        | Poor        | Good             | Fair        | Poor        |
|           | $\Phi_c$                    | 1                | 0.95        | 0.85        | 1                | 0.95        | 0.85        |
|           | C [k]                       | 615              | 615         | 615         | 567              | 567         | 567         |
| <b>RF</b> | <b>pedestrian inventory</b> | <b>1.25</b>      | <b>1.25</b> | <b>1.25</b> | <b>1.08</b>      | <b>1.08</b> | <b>1.08</b> |
| <b>RF</b> | <b>pedestrian operating</b> | <b>1.62</b>      | <b>1.62</b> | <b>1.62</b> | <b>1.40</b>      | <b>1.40</b> | <b>1.40</b> |
| <b>RF</b> | <b>vehicle inventory</b>    | <b>8.58</b>      | <b>8.58</b> | <b>8.58</b> | <b>7.38</b>      | <b>7.38</b> | <b>7.38</b> |
| <b>RF</b> | <b>vehicle operating</b>    | <b>11.1</b>      | <b>11.1</b> | <b>11.1</b> | <b>9.57</b>      | <b>9.57</b> | <b>9.57</b> |

## North Suspension Bridge Load Rating (LRFR Method)

### Spreader Bars

|                      |   |
|----------------------|---|
| Size                 | 3 <sup>1</sup> / <sub>2</sub> " Std. Pipe |
| A <sub>g</sub>       | 2.51 in <sup>2</sup>                      |
| L                    | 9.5 ft                                    |
| D <sub>outside</sub> | 4 in <sup>2</sup>                         |
| d <sub>inside</sub>  | 3.55 in <sup>2</sup>                      |
| t                    | 0.226 in                                  |
| r <sub>s</sub>       | 1.34 in                                   |
| F <sub>y</sub>       | 50 ksi                                    |
| E                    | 29000 ksi                                 |

### Dead Loads

|              |                  |        |                        |
|--------------|------------------|--------|------------------------|
| <i>Axial</i> | P <sub>max</sub> | 15.5 k | (from CSiBridge Model) |
|--------------|------------------|--------|------------------------|

### Live Loads

Pedestrian and Vehicular loads act separately

|                    |    |        |                            |
|--------------------|----|--------|----------------------------|
| <u>Pedestrian:</u> | PL | 90 psf | AASHTO LRFD Ped Bridge 3.1 |
|--------------------|----|--------|----------------------------|

|              |                  |        |                        |
|--------------|------------------|--------|------------------------|
| <i>Axial</i> | P <sub>max</sub> | 11.3 k | (from CSiBridge Model) |
|--------------|------------------|--------|------------------------|

|                   |               |         |         |
|-------------------|---------------|---------|---------|
| <u>Vehicular:</u> | LL            | Truck 1 | Truck 2 |
|                   | Total         | 16.2    | 21.19 k |
| <i>Weight</i>     | Axle 1 Wheels | 6.08    | 7.95 k  |
|                   | Axle 2 Wheels | 2.03    | 2.65 k  |
|                   | wheel spacing | 6       | 6 ft    |
|                   | axle spacing  | 6.58    | 8.25 ft |

|              |                  |        |  |
|--------------|------------------|--------|--|
| <i>Axial</i> | P <sub>max</sub> | 1.64 k | (from CSiBridge Model, Truck 2 controls) |
|--------------|------------------|--------|--|

### Capacity

|   |                                     |                    |
|---|-------------------------------------|--------------------|
| <u>Compression Resistance</u>                   |                                     | AASHTO 6.9.4.1.1   |
| K   | 0.65                                | AASHTO 4.6.2.5     |
| Φ <sub>c</sub>                                  | 0.9                                 | AASHTO 6.5.4.2     |
| P <sub>e</sub> =                                | $\frac{\pi^2 E A_g}{(K L / r_s)^2}$ | AASHTO 6.9.4.1.2-1 |
| P <sub>o</sub> = QF <sub>y</sub> A <sub>g</sub> |                                     | AASHTO 6.9.4.1.1   |
| D   | 4 in                                |                    |
| t   | 0.226 in                            |                    |
| D/t   | 17.7                                | → Nonslender       |
| 0.11*E/F <sub>y</sub>                           | 63.8                                |                    |
| Q   | 1.0                                 | AASHTO 6.9.4.2     |



$$\begin{aligned}
 P_e &= 235 \text{ k} && \text{AASHTO 6.9.4.1.2-1} \\
 P_o &= 126 \text{ k} && \text{AASHTO 6.9.4.1.1} \\
 P_e/P_o &= 1.87 \\
 P_e/P_o > 0.44 &\rightarrow \\
 P_n &= (0.658^{(P_o/P_e)})P_e && \text{AASHTO 6.9.4.1.1-1} \\
 P_n &= 100 \text{ k} \\
 \Phi P_n &= 90.3 \text{ k}
 \end{aligned}$$

### Rating Factors

$$RF = \frac{(C - V_{DC}DC - V_{DW}DW + / - V_P P)}{V_{LL}LL(1+IM)} \quad \text{AASHTO MBE 6A.4.2.1-1}$$

$$\begin{aligned}
 C_{Str-I} &= \Phi_c \Phi_s \Phi_n R_n && \text{AASHTO MBE 6A.4.2.1-2} \\
 \Phi_c \Phi_s &\geq 0.85 && \text{AASHTO MBE 6A.4.2.1-3} \\
 \Phi_s &= 1 && \text{AASHTO MBE 6A.4.2.4}
 \end{aligned}$$

$$\begin{aligned}
 V_{DC} &= 1.25 \\
 V_{LL \text{ inv.}} &= 1.75 \\
 V_{LL \text{ op.}} &= 1.35 \\
 IM &= 0 && \text{AASHTO LRFD Ped. Bridge Manual 3.2}
 \end{aligned}$$

### Axial

| Condition                                 | Good        | Fair        | Poor        |
|---|-------------|-------------|-------------|
| $\Phi_c$                                  | 1           | 0.95        | 0.85        |
| C [k]                                     | 90.3        | 85.8        | 76.8        |
| <b>RF</b> <sub>pedestrian inventory</sub> | <b>3.59</b> | <b>3.36</b> | <b>2.91</b> |
| <b>RF</b> <sub>pedestrian operating</sub> | <b>4.66</b> | <b>4.36</b> | <b>3.77</b> |
| <b>RF</b> <sub>vehicle inventory</sub>    | <b>24.8</b> | <b>23.2</b> | <b>20.0</b> |
| <b>RF</b> <sub>vehicle operating</sub>    | <b>32.1</b> | <b>30.0</b> | <b>26.0</b> |

## North Suspension Bridge Load Rating (LRFR Method)

### Hanger Bolts

|                       |                      |  |
|-----------------------|----------------------|--|
| d                     | 0.75 in              |  |
| d <sub>actual</sub>   | 0.50 in              | (Accounts for corrosion)                 |
| d <sub>threads</sub>  | 0.65 in              | (Based on equation AASTHO 6.13.2.10.2-1) |
| A <sub>b</sub>        | 0.44 in <sup>2</sup> |  |
| A <sub>b actual</sub> | 0.20 in <sup>2</sup> |  |
| F <sub>ub</sub>       | 120 ksi              | (A325 Bolts)                             |
| E                     | 29000 ksi            |  |

**Dead Loads** Force in hanger bolts = hanger strand force divided by four (number of bolts/hanger)

|              |                  |        |                        |
|--------------|------------------|--------|------------------------|
| <i>Axial</i> | P <sub>max</sub> | 2.21 k | (from CSiBridge Model) |
|--------------|------------------|--------|------------------------|

**Live Loads** Pedestrian and Vehicular loads act separately

Pedestrian: PL 90 psf AASHTO LRFD Ped Bridge 3.1

|              |                  |        |                        |
|--------------|------------------|--------|------------------------|
| <i>Axial</i> | P <sub>max</sub> | 1.70 k | (from CSiBridge Model) |
|--------------|------------------|--------|------------------------|

Vehicular:

|               |         |         |
|---------------|---------|---------|
| LL            | Truck 1 | Truck 2 |
| Total         | 16.2    | 21.19 k |
| <i>Weight</i> |         |         |
| Axle 1 Wheels | 6.08    | 7.95 k  |
| Axle 2 Wheels | 2.03    | 2.65 k  |
| wheel spacing | 6       | 6 ft    |
| axle spacing  | 6.58    | 8.25 ft |

|              |                  |        |  |
|--------------|------------------|--------|--|
| <i>Axial</i> | P <sub>max</sub> | 0.41 k | (from CSiBridge Model, Truck 2 controls) |
|--------------|------------------|--------|--|

### Capacity

#### Tensile Resistance

If d<sub>threads</sub> < d<sub>actual</sub> :

$$\Phi T_n = \Phi_t 0.76 A_b F_{ub} \quad \text{AASHTO 6.13.2.10.2-1}$$

If d<sub>threads</sub> > d<sub>actual</sub> :

$$\Phi T_n = \Phi_t A_{b \text{ actual}} F_{ub} \quad \text{AASHTO 6.13.2.10.2-1}$$

$$\Phi_t = 0.8$$

$$\Phi T_n = 18.8 \text{ k}$$

## Rating Factors

$$RF = \frac{(C - V_{DC}DC - V_{DW}DW + / - V_P P)}{V_{LL}LL(1+IM)}$$

AASHTO MBE 6A.4.2.1-1

$$C_{Str-I} = \Phi_c \Phi_s \Phi_n R_n$$

$\Phi_c \Phi_s \geq 0.85$

$\Phi_s$  1

AASHTO MBE 6A.4.2.1-2  
AASHTO MBE 6A.4.2.1-3  
AASHTO MBE 6A.4.2.4

|                       |      |                                    |
|-----------------------|------|------------------------------------|
| $V_{DC}$              | 1.25 |                                    |
| $V_{LL \text{ inv.}}$ | 1.75 |                                    |
| $V_{LL \text{ op.}}$  | 1.35 |                                    |
| IM                    | 0    | AASHTO LRFD Ped. Bridge Manual 3.2 |

## Axial

| Condition                                | Good        | Fair        | Poor        |
|--|-------------|-------------|-------------|
| $\Phi_c$                                 | 1           | 0.95        | 0.85        |
| C [k]                                    | 18.8        | 17.9        | 16.0        |
| <b>RF<sub>pedestrian inventory</sub></b> | <b>5.41</b> | <b>5.10</b> | <b>4.46</b> |
| <b>RF<sub>pedestrian operating</sub></b> | <b>7.02</b> | <b>6.61</b> | <b>5.78</b> |
| <b>RF<sub>vehicle inventory</sub></b>    | <b>22.3</b> | <b>21.0</b> | <b>18.4</b> |
| <b>RF<sub>vehicle operating</sub></b>    | <b>28.9</b> | <b>27.2</b> | <b>23.8</b> |

## North Suspension Bridge Load Rating (LRFR Method)

### Concrete Pylons

|                   |                      |
|-------------------|----------------------|
| d                 | 30 in                |
| $A_g$             | 707 in <sup>2</sup>  |
| $A_{bars}$        | 1.56 in <sup>2</sup> |
| $N_{bars}$        | 22 in                |
| $A_{spiral bars}$ | 0.11 in <sup>2</sup> |
| $p_{spiral bars}$ | 1.75 in              |
| $f_y$             | 60 ksi               |
| clear cov.        | 1.5                  |
| $f'_c$            | 5 ksi                |
| $\gamma_c$        | 0.16 kcf             |
| $\beta_1$         | 0.85                 |
| L                 | 52.25 ft             |

### Dead Loads

|        |            |          |                        |
|--------|------------|----------|------------------------|
| Weight | $W_{DL} =$ | 41.0 k   |                        |
| Moment | $M_{DL} =$ | 288 k-in |                        |
| Axial  | $P_{DL} =$ | 435 k    | (From CSiBridge Model) |

### Live Loads

Pedestrian and Vehicular loads act separately

|                    |            |             |                            |
|--------------------|------------|-------------|----------------------------|
| <u>Pedestrian:</u> | PL         | 90 psf      | AASHTO LRFD Ped Bridge 3.1 |
| Weight             | $W_{PL} =$ | 115 k/pylon |                            |
| Moment             | $M_{PL} =$ | 3300 k-in   |                            |
| Axial              | $P_{PL} =$ | 284 k       | (From CSiBridge Model)     |

|                   |               |         |         |
|-------------------|---------------|---------|---------|
| <u>Vehicular:</u> | LL            | Truck 1 | Truck 2 |
|                   | Total         | 16.2    | 21.19 k |
| Weight            | Axle 1 Wheels | 6.08    | 7.95 k  |
|                   | Axle 2 Wheels | 2.03    | 2.65 k  |
|                   | wheel spacing | 6       | 6 ft    |
|                   | axle spacing  | 6.58    | 8.25 ft |

|        |            |          |                                |
|--------|------------|----------|--------------------------------|
| Moment | $M_{LL} =$ | 481 k-in | (From CSiBridge Model, Truck 2 |
| Axial  | $P_{LL} =$ | 42.2 k   | controls)                      |

## Capacity

### Compression + Flexure

AASHTO MBE Appendix G6A

$$e_1 = M_{LL}/P_{LL}$$

$$e_{1 \text{ ped.}} = 11.6 \text{ in}$$

$$e_{1 \text{ vehicle}} = 11.4 \text{ in}$$

$$e_2 = M_{DL}/P_{DL}$$

$$e_2 = 0.66 \text{ in}$$

$$\Phi M_{n \text{ ped.}} = 14400 \text{ k-in}$$


$$\Phi M_{n \text{ veh.}} = 14100 \text{ k-in}$$

$$\Phi P_{n \text{ ped.}} = 1650 \text{ k}$$


$$\Phi P_{n \text{ veh.}} = 1750 \text{ k}$$

(From SpColumn)

*\*The capacity for concrete elements in compression and bending is determined from a P-M interaction diagram. The axial and bending capacities are assumed to be the values at the edge of the interaction diagram along the line that connects the factored dead and the factored live plus dead combined loading responses. Rating factors are calculated for both the max axial and bending conditions.*







## Rating Factors

$$RF = \frac{(C - V_{DC}DC - V_{DW}DW + / - V_P P)}{V_{LL}LL(1+IM)}$$
AASHTO MBE 6A.4.2.1-1

$$C_{Str-I} = \Phi_c \Phi_s \Phi_n R_n$$
AASHTO MBE 6A.4.2.1-2

$$\Phi_c \Phi_s \geq 0.85$$
AASHTO MBE 6A.4.2.1-3

$$\Phi_s = 0.85$$
AASHTO MBE 6A.4.2.4

$$V_{DC} = 1.25$$

$$V_{LL \text{ inv.}} = 1.75$$

$$V_{LL \text{ op.}} = 1.35$$

$$IM = 0$$
AASHTO LRFD Ped. Bridge Manual 3.2

### Flexure

| Condition                                | Good        | Fair        | Poor        |
|--|-------------|-------------|-------------|
| $\Phi_c$                                 | 1           | 0.95        | 0.85        |
| C [k-in]                                 | 12240       | 12240       | 12240       |
| <b>RF<sub>pedestrian inventory</sub></b> | <b>2.06</b> | <b>2.06</b> | <b>2.06</b> |
| <b>RF<sub>pedestrian operating</sub></b> | <b>2.67</b> | <b>2.67</b> | <b>2.67</b> |
| C [k-in]                                 | 11985       | 11985       | 11985       |
| <b>RF<sub>vehicle inventory</sub></b>    | <b>13.8</b> | <b>13.8</b> | <b>13.8</b> |
| <b>RF<sub>vehicle operating</sub></b>    | <b>17.9</b> | <b>17.9</b> | <b>17.9</b> |

### Axial

| Condition                                | Good        | Fair        | Poor        |
|--|-------------|-------------|-------------|
| $\Phi_c$                                 | 1           | 0.95        | 0.85        |
| C [k]                                    | 1403        | 1403        | 1403        |
| <b>RF<sub>pedestrian inventory</sub></b> | <b>1.73</b> | <b>1.73</b> | <b>1.73</b> |
| <b>RF<sub>pedestrian operating</sub></b> | <b>2.24</b> | <b>2.24</b> | <b>2.24</b> |
| C [k]                                    | 1488        | 1488        | 1488        |
| <b>RF<sub>vehicle inventory</sub></b>    | <b>12.8</b> | <b>12.8</b> | <b>12.8</b> |
| <b>RF<sub>vehicle operating</sub></b>    | <b>16.6</b> | <b>16.6</b> | <b>16.6</b> |

## North Suspension Bridge Load Rating (LRFR Method)

### Summary

\*Floorbeams are in fair condition ( $\Phi_c = 0.95$ ) and Deck is in poor condition ( $\Phi_c = 0.85$ )

\*All other members are in good condition ( $\Phi_c = 1$ )

| Controlling Rating Factor & Failure Force | Pedestrian     |             |             | Vehicle    |             |             |
|---|----------------|-------------|-------------|------------|-------------|-------------|
|   | Force          | Inventory   | Operating   | Force      | Inventory   | Operating   |
| <b>Deck</b>                               | <b>Flexure</b> | <b>0.51</b> | <b>0.66</b> | <i>N/A</i> | <i>N/A</i>  | <i>N/A</i>  |
| <b>Girders</b>                            | Flexure        | 3.30        | 4.28        | Flexure    | <b>1.45</b> | <b>1.88</b> |
| <b>Floorbeams</b>                         | Flexure        | 56.4        | 73.1        | Flexure    | 23.9        | 31.0        |
| <b>Crossbracing</b>                       | Flexure        | 18.6        | 24.2        | Flexure    | 5.76        | 7.47        |
| <b>Hanger Cables</b>                      | Axial          | 2.39        | 3.10        | Axial      | 9.83        | 12.7        |
| <b>Main Cables</b>                        | Axial          | 1.30        | 1.68        | Axial      | 8.79        | 11.4        |
| <b>Backstay Cables</b>                    | Axial          | 1.08        | 1.40        | Axial      | 7.38        | 9.57        |
| <b>Spreader Bars</b>                      | Axial          | 3.59        | 4.66        | Axial      | 24.8        | 32.1        |
| <b>Hanger Bolts</b>                       | Axial          | 4.46        | 5.78        | Axial      | 18.4        | 23.8        |
| <b>Pylons</b>                             | Axial          | 1.73        | 2.24        | Axial      | 12.8        | 16.6        |

# APPENDIX D

PHOTOGRAPH LOG

PHOTOGRAPH CONTACT SHEET

|                      |                                    |      |             |           |
|----------------------|------------------------------------|------|-------------|-----------|
| Project              | Riverfront Park Bridges Inspection | By   | M. Frymoyer | Sheet No. |
| Location             | Spokane                            | Date | 9/26/2014   | 1 OF10    |
| Client               | City of Spokane                    |      |             | Job No.   |
| Inspection Photo Log |                                    |      |             | 114176.12 |

Bridge Name: North Suspension Bridge

Date of Inspection: 9/3/14-9/5/14

| Camera No. | Photo No. | Location   | Notes   | By  |
|------------|-----------|------------|---|-----|
| A          | 262       | H1 - H2 RT | Loose railing cover plate                           | MLF |
| A          | 263       | H1 - H2 RT | Loose railing cover plate                           | MLF |
| A          | 318       | H1 RT      | Debris on bottom flanger of girder                  | JPG |
| A          | 320       | H1 RT      | Moderate corrosion on floorbeam                     | JPG |
| A          | 321       | H1 RT      | SIP deck form is corroded, exposed/missing concrete | JPG |
| A          | 322       | H1 RT      | Floorbeam has minor corrosion                       | JPG |
| A          | 324       | H1 RT      | Inside hanger bolt connection moderate corrosion    | JPG |
| A          | 325       | H1 RT      | Girder, typical                                     | JPG |
| A          | 326       | H1 RT      | Abutment/floorbeam                                  | JPG |
| A          | 327       | H1 RT      | Abutment/floorbeam                                  | JPG |
| A          | 328       | H1 RT      | Abutment/floorbeam                                  | JPG |
| A          | 329       | H2 RT      | Girder good condition                               | JPG |
| A          | 330       | H2 RT      | Girder good condition                               | JPG |
| A          | 331       | H2 RT      | SIP deck form is corroded                           | JPG |
| A          | 332       | H2 RT      | Floorbeam is corroded                               | JPG |
| A          | 335       | H2 RT      | Minor corrosion inside hanger bolt connection       | JPG |
| A          | 337       | H3 RT      | Heavily corroded floorbeam                          | JPG |
| A          | 338       | H3 RT      | Braces in good condition                            | JPG |
| A          | 339       | H3 RT      | Corroded formwork                                   | JPG |
| A          | 340       | H3 RT      | Inside hanger bolt connection moderate corrosion    | JPG |
| A          | 341       | H4 RT      | Girder splice in good condition                     | JPG |
| A          | 342       | H4 RT      | Girder splice in good condition                     | JPG |
| A          | 343       | H4 RT      | Floorbeam has minor corrosion                       | JPG |
| A          |           |            |   |     |
| A          | 345       | H4 RT      | Inside hanger bolt connection moderate corrosion    | JPG |
| A          | 347       | H4 RT      | Corroded formwork                                   | JPG |
| A          | 349       | H5 RT      | Debris on bottom flanger of girder                  | JPG |
| A          | 350       | H5 RT      | Debris on bottom flanger of girder                  | JPG |
| A          | 351       | H5 RT      | Floorbeam has heavy corrosion                       | JPG |
| A          | 352       | H5 RT      | Corroded formwork                                   | JPG |
| A          | 353       | H5 RT      | Inside of girder                                    | JPG |
| A          | 355       | H5 RT      | Heavy corrosioin inside hanger bolt connection      | JPG |
| A          | 356       | H6 RT      | Floorbeam has heavy corrosion                       | JPG |
| A          | 357       | H6 RT      | Heavy corrosioin inside hanger bolt connection      | JPG |
| A          | 358       | H6 RT      | Heavy corrosioin inside hanger bolt connection      | JPG |
| A          | 359       | H6 RT      | Girder splice in good condition                     | JPG |
| A          | 361       | H6 RT      | Girder splice in good condition                     | JPG |
| A          | 362       | H6 RT      | Corroded formwork                                   | JPG |
| A          | 368       | H7 LT      | No erection bolts in connectioin                    | JPG |
| A          | 369       | H7 LT      | Floorbeam is heavily corroded                       | JPG |
| A          | 370       | H7 LT      | Flaking in girder web                               | JPG |
| A          | 372       | H7 LT      | Corroded formwork                                   | JPG |
| A          | 373       | H7 LT      | Inside hanger bolt connection moderate corrosion    | JPG |
| A          | 374       | H7 LT      | Inside hanger bolt connection moderate corrosion    | JPG |
| A          | 375       | H9 LT      | No erection bolt in connectioin                     | JPG |

|   |                      |                                    |  |      |             |           |           |
|---|----------------------|------------------------------------|--|------|-------------|-----------|-----------|
|  <p>1601 Fifth Avenue, Suite 1600 Seattle, WA 98101<br/>(206) 622-5822 fax (206) 622-8130</p> | Project              | Riverfront Park Bridges Inspection |  | By   | M. Frymoyer | Sheet No. |           |
|   | Location             | Spokane                            |  | Date | 9/26/2014   |           | 2 OF10    |
|   | Client               | City of Spokane                    |  |      |             | Job No.   |           |
|   | Inspection Photo Log |                                    |  |      |             |           | 114176.12 |


  

Bridge Name: North Suspension Bridge

Date of Inspection: 9/3/14-9/5/14

| Camera No. | Photo No. | Location   | Notes   | By  |
|------------|-----------|------------|---|-----|
| A          | 376       | H9 LT      | No erection bolt in connection                                | JPG |
| A          | 377       | H9 LT      | No erection bolt in connection                                | JPG |
| A          | 378       | H9 LT      | Inside web of girder  | JPG |
| A          | 379       | H9 LT      | Floorbeam is heavily corroded                                 | JPG |
| A          | 380       | H9 LT      | SIP deck is corroded, concrete deck is exposed                | JPG |
| A          | 381       | H9 LT      | Inside hanger bolt connection moderate corrosion              | JPG |
| A          | 382       | H10 LT     | Flaking steel at bottom of connection plate                   | MLF |
| A          | 383       | H10 LT     | Loose erection bolt at connection                             | MLF |
| A          | 384       | H11 LT     | Missing/loose erection bolts                                  | MLF |
| A          | 385       | H11 RT     | Missing erection bolts  | MLF |
| A          | 386       | H12 LT     | Flaking steel at bottom of connection plate                   | MLF |
| A          | 387       | H12 LT     | Corrosion at girder - lateral brace connection                | MLF |
| A          | 389       | H12 LT     | Splice plate, bolts have minor corrosion                      | MLF |
| A          | 390       | H13 LT     | SIP deck is corroded, concrete deck is exposed                | JPG |
| A          | 392       | H14 LT     | Girder splice   | JPG |
| A          | 393       | H14 LT     | Debris at lateral brace - girder connection                   | JPG |
| A          | 394       | H14 LT     | Debris at lateral brace - girder connection                   | JPG |
| A          | 395       | H14 LT     | Floorbeam minor corrosion                                     | JPG |
| A          | 396       | H15 LT     | SIP deck is corroded, concrete deck is exposed                | JPG |
| A          | 397       | H16 LT     | Heavily corroded floorbeam                                    | JPG |
| A          | 398       | H16 LT     | Heavily corroded floorbeam                                    | JPG |
| A          | 399       | H16 LT     | Girder splice   | JPG |
| A          | 401       | H16 LT     | Inside hanger bolt connection moderate corrosion              | JPG |
| A          | 402       | H16 LT     | SIP deck is corroded, concrete deck is exposed                | JPG |
| A          | 403       | H16 LT     | Corrosion at girder - lateral brace connection                | JPG |
| A          | 404       | H17 LT     | Inside hanger bolt connection moderate corrosion              | JPG |
| A          | 405       | H17 LT     | Floorbeam minor corrosion                                     | JPG |
| A          | 406       | H17 LT     | Corrosion at girder - lateral brace connection                | JPG |
| A          | 407       | H17 LT     | SIP deck is corroded, concrete deck is exposed                | JPG |
| A          | 408       | H17 LT     | Girder at abutment  | JPG |
| A          | 409       | Pier 2     | Rock wall abutment  | JPG |
| A          | 427       | Pier 1     | Right girder at bearing                                       | MLF |
| A          | 428       | Pier 1     | Abutment  | MLF |
| A          | 429       | Pier 1     | Heavy corrosion top flange of right girder                    | MLF |
| A          | 430       | Pier 1     | Heavy corrosion floorbeam                                     | MLF |
| A          | 431       | Pier 1     | Bearing right girder  | MLF |
|            |           |            |   |     |
| C          | 2297      | H1 RT deck | Typical deck transverse crack at 1/2 or 1/3 point every panel |     |
| C          | 2298      | H1 RT deck | Typical spalling, cracking around hangers at curb             |     |
| C          | 2299      | H3 RT deck | Spalling and exposed rebar at curb                            |     |
| C          | 2300      | H8 RT      | Curb is spalling at hanger connection                         | JPG |
| C          | 2301      | H8 RT      | Spall in deck   | JPG |
| C          | 2302      | H8 RT      | Spall in deck   | JPG |
| C          | 2303      | H11 RT     | Spall in deck   | JPG |
| C          | 2304      | H14 RT     | Spall in deck with exposed reinforcement                      | JPG |



|   |                      |                                    |  |      |             |           |           |
|---|----------------------|------------------------------------|--|------|-------------|-----------|-----------|
|  <p>1601 Fifth Avenue, Suite 1600 Seattle, WA 98101<br/>(206) 622-5822 fax (206) 622-8130</p> | Project              | Riverfront Park Bridges Inspection |  | By   | M. Frymoyer | Sheet No. |           |
|   | Location             | Spokane                            |  | Date | 9/26/2014   |           | 3 OF10    |
|   | Client               | City of Spokane                    |  |      |             | Job No.   |           |
|   | Inspection Photo Log |                                    |  |      |             |           | 114176.12 |

Bridge Name: North Suspension Bridge

Date of Inspection: 9/3/14-9/5/14

| Camera No. | Photo No. | Location | Notes  | By  |
|------------|-----------|----------|--|-----|
| C          | 2305      | H14 RT   | Spall in deck with exposed reinforcement         | JPG |
| C          | 2306      | H16 RT   | Deck spalling at joint                           | JPG |
| C          | 2307      | Pier 2   | Floorbeam / abutment anchors                     | JPG |
| C          | 2309      | Pier 2   | Floorbeam / abutment anchors                     | JPG |
| C          | 2310      | Pier 2   | Floorbeam / abutment anchors                     | JPG |
| C          | 2311      | Pier 2   | Girder/lateral bracing connection                | JPG |
| C          | 2312      | Pier 2   | Girder bearing                                   | JPG |
| C          | 2313      | H7 LT    | Plugged drain                                    | JPG |
| C          | 2314      | H7 LT    | Exposed reinforcement in curb                    | JPG |
| C          | 2315      | H7 LT    | Plugged drain                                    | JPG |
| C          | 2316      | H7 LT    | Drains are missing grate                         | JPG |
| C          | 2317      | Pier 1   | Expansion joint                                  | JPG |
| C          | 2318      | Pier 1   | Expansion joint                                  | JPG |
| C          | 2319      | General  | Deck, looking south                              | JPG |
| C          | 2320      | General  | Deck, looking south                              | JPG |
| C          | 2321      | Pier 2   | Expansion joint                                  | JPG |
|            |           |          |  |     |
|            |           |          |  |     |
| 6          | 1215      | H1 LT    | Outside view of girder                           | MLF |
| 6          | 1216      | H1 LT    | Floorbeam  | MLF |
| 6          | 1218      | H1 LT    | Abutment/bracing                                 | MLF |
| 6          | 1219      | H1 LT    | Inside of girder corrosion at abutment           | MLF |
| 6          | 1220      | H1 LT    | Inside of girder corrosion at abutment           | MLF |
| 6          | 1221      | H1 LT    | Inside of girder corrosion at abutment           | MLF |
| 6          | 1222      | H2 LT    | Debris at lateral brace connection               | MLF |
| 6          | 1223      | H2 LT    | Corrosion in floorbeam                           | MLF |
| 6          | 1224      | H2 RT    | Girder splice                                    | MLF |
| 6          | 1225      | H2 LT    | Girder splice                                    | MLF |
| 6          | 1226      | H2 LT    | Girder splice                                    | MLF |
| 6          | 1227      | H1 LT    | SIP deck corroded, deck spall                    | MLF |
| 6          | 1228      | H3 LT    | Floorbeam corrosion                              | MLF |
| 6          | 1229      | H3 LT    | Flaking bottom flange girder                     | MLF |
| 6          | 1230      | H3 LT    | Flaking bottom flange girder                     | MLF |
| 6          | 1231      | H3 LT    | SIP deck corrosion                               | MLF |
| 6          | 1232      | H4 LT    | Girder splice                                    | MLF |
| 6          | 1233      | H5 LT    | Girder splice                                    | MLF |
| 6          | 1234      | H5 LT    | Floorbeam corrosion                              | MLF |
| 6          | 1235      | H5 LT    | Floorbeam - girder corrosion                     | MLF |
| 6          | 1236      | H5 LT    | Girder bottom flanger corrosion                  | MLF |
| 6          | 1237      | H5 LT    | Inside hanger bolt connection moderate corrosion | MLF |
| 6          | 1240      | H6 LT    | Outside hanger bolt connection                   | TW  |
| 6          | 1241      | H6 LT    | SIP deck corrosion                               | TW  |
| 6          | 1242      | H6 LT    | SIP deck corrosion                               | TW  |
| 6          | 1248      | H6 LT    | Lateral bracing connection                       | TW  |
| 6          | 1249      | H6 LT    | Girder splice                                    | TW  |

|   |                      |                                    |      |             |           |
|---|----------------------|------------------------------------|------|-------------|-----------|
|  <b>kpff</b> Consulting Engineers<br>1601 Fifth Avenue, Suite 1600 Seattle, WA 98101<br>(206) 622-5822 fax (206) 622-8130 | Project              | Riverfront Park Bridges Inspection | By   | M. Frymoyer | Sheet No. |
|   | Location             | Spokane                            | Date | 9/26/2014   | 4 OF10    |
|   | Client               | City of Spokane                    |      |             | Job No.   |
|   | Inspection Photo Log |                                    |      |             | 114176.12 |

Bridge Name: North Suspension Bridge

Date of Inspection: 9/3/14-9/5/14

| Camera No. | Photo No. | Location | Notes   | By |
|------------|-----------|----------|---|----|
| 6          | 1250      | H6 LT    | Floorbeam minor corrosion                             |    |
| 6          | 1251      | H6 LT    | Bottom of girder                                      | TW |
| 6          | 1252      | H6 LT    | General view floor framing                            | TW |
| 6          | 1253      | H6 LT    | General view floor framing                            | TW |
| 6          | 1254      | H6 LT    | General view floor framing                            | TW |
| 6          | 1255      | H6 LT    | General view of deck                                  | TW |
| 6          | 1256      | H7 RT    | Outside hanger bolt connection minor corrosion        | BK |
| 6          | 1257      | H7 RT    | Floorbeam - girder connection                         | BK |
| 6          | 1258      | H7 RT    | Floorbeam - girder connection                         | BK |
| 6          | 1259      | H7 RT    | Heavily corroded SIP deck form and floorbeam          | BK |
| 6          | 1260      | H7 RT    | Inside hanger bolt connection minor corrosion         | BK |
| 6          | 1261      | H7 RT    | Debris in connection                                  | BK |
| 6          | 1262      | H8 RT    | Outside hanger bolt connection minor corrosion        | BK |
| 6          | 1263      | H8 RT    | Girder splice   | BK |
| 6          | 1264      | H8 RT    | Outside hanger bolt connection minor corrosion        | BK |
| 6          | 1265      | H8 RT    | Floorbeam - girder connection                         | BK |
| 6          | 1266      | H8 RT    | Inside hanger bolt connection minor corrosion         | BK |
| 6          | 1267      | H8 LT    | Floorbeam - girder connection                         | BK |
| 6          | 1268      | H8 LT    | Floorbeam - girder - lateral brace connection         | BK |
| 6          | 1269      | H9 RT    | Outside hanger bolt connection minor corrosion        | BK |
| 6          | 1270      | H9 RT    | Outside hanger bolt connection minor corrosion        | BK |
| 6          | 1271      | H9 RT    | Outside hanger bolt connection minor corrosion        | BK |
| 6          | 1272      | H9 RT    | Outside hanger bolt connection minor corrosion        | BK |
| 6          | 1273      | H9 RT    | Heavily corroded connection floorbeam - lateral brace | BK |
| 6          | 1274      | H9 RT    | Corroded floorbeam                                    | BK |
| 6          | 1275      | H9 RT    | Inside hanger bolt connection moderate corrosion      | BK |
| 6          | 1276      | H9 RT    | Inside hanger bolt connection moderate corrosion      | BK |
| 6          | 1277      | H10 RT   | Floorbeam - girder connection                         | BK |
| 6          | 1278      | H10 RT   | Inside hanger bolt connection minor corrosion         | BK |
| 6          | 1279      | H10 RT   | Inside hanger bolt connection minor corrosion         | BK |
| 6          | 1280      | H10 RT   | Floorbeam - girder connection                         | BK |
| 6          | 1281      | H10 RT   | SIP deck form corrosion                               | BK |
| 6          | 1282      | H11 RT   | Outside hanger bolt connection minor corrosion        | BK |
| 6          | 1283      | H11 RT   | Floorbeam - lateral brace connection                  | BK |
| 6          | 1284      | H11 RT   | Floorbeam - lateral brace connection                  | BK |
| 6          | 1285      | H11 RT   | Inside hanger bolt connection minor corrosion         | BK |
| 6          | 1286      | H11 RT   | SIP deck form corrosion                               | BK |
| 6          | 1287      | H12 RT   | Outside hanger bolt connection minor corrosion        | BK |
| 6          | 1288      | H12 RT   | Girder splice   | BK |
| 6          | 1289      | H12 RT   | Floorbeam - girder connection                         | BK |
| 6          | 1290      | H12 RT   | SIP deck form corrosion                               | BK |
| 6          | 1291      | H13 RT   | Outside hanger bolt connection minor corrosion        | BK |
| 6          | 1292      | H13 RT   | Floorbeam moderate corrosion                          | BK |
| 6          | 1293      | H13 RT   | Inside hanger bolt connection minor corrosion         | BK |
| 6          | 1294      | H13 RT   | Lateral brace - girder connection                     | BK |


|   |                      |                                    |  |      |             |           |
|---|----------------------|------------------------------------|--|------|-------------|-----------|
|  Consulting Engineers<br>1601 Fifth Avenue, Suite 1600 Seattle, WA 98101<br>(206) 622-5822 fax (206) 622-8130 | Project              | Riverfront Park Bridges Inspection |  | By   | M. Frymoyer | Sheet No. |
|   | Location             | Spokane                            |  | Date | 9/26/2014   | 5 OF10    |
|   | Client               | City of Spokane                    |  |      |             | Job No.   |
|   | Inspection Photo Log |                                    |  |      |             |           |

Bridge Name: North Suspension Bridge

Date of Inspection: 9/3/14-9/5/14

| Camera No. | Photo No. | Location | Notes   | By |
|------------|-----------|----------|---|----|
| 6          | 1295      | H13 RT   | Lateral brace - girder connection                 | BK |
| 6          | 1296      | H13 RT   | Debris in connection                              | BK |
| 6          | 1297      | H14 RT   | Outside hanger bolt connection minor corrosion    | BK |
| 6          | 1298      | H14 RT   | Girder splice                                     | BK |
| 6          | 1299      | H14 RT   | Girder  | BK |
| 6          | 1300      | H14 RT   | Heavy corrosion floorbeam                         | BK |
| 6          | 1301      | H14 RT   | Heavy corrosion floorbeam                         | BK |
| 6          | 1302      | H14 RT   | Heavy corrosion floorbeam                         | BK |
| 6          | 1303      | H14 RT   | SIP deck form corrosion                           | BK |
| 6          | 1304      | H15 RT   | Girder web/top flange flaking                     | BK |
| 6          | 1305      | H15 RT   | Floorbeam - lateral brace connection corroded     | BK |
| 6          | 1306      | H15 RT   | Floorbeam - lateral brace connection corroded     | BK |
| 6          | 1307      | H15 RT   | Debris in connection                              | BK |
| 6          | 1308      | H15 RT   | Heavy corrosion floorbeam, hanger bolt connection | BK |
|            |           |          |   |    |
| 7          | 5366      | H16 RT   | Outside hanger bolt connection                    | PG |
| 7          | 5367      | H16 RT   | Girder  | PG |
| 7          | 5368      | H16 RT   | Girder  | PG |
| 7          | 5369      | H16 RT   | Girder  | PG |
| 7          | 5370      | H16 RT   | Girder splice                                     | PG |
| 7          | 5371      | H16 RT   | Inside hanger bolt connection                     | PG |
| 7          | 5372      | H16 RT   | Inside hanger bolt connection                     | PG |
| 7          | 5373      | H16 RT   | Inside view of girder                             | PG |
| 7          | 5374      | H16 RT   | Inside view of girder                             | PG |
| 7          | 5375      | H16 RT   | SIP deck form corrosion                           | PG |
| 7          | 5376      | H17 RT   | Outside hanger bolt connection                    | PG |
| 7          | 5377      | H17 RT   | Outside hanger bolt connection                    | PG |
| 7          | 5378      | H17 RT   | Girder  | PG |
| 7          | 5379      | H17 RT   | Girder  | PG |
| 7          | 5380      | H17 RT   | Girder  | PG |
| 7          | 5381      | H17 RT   | Girder  | PG |
| 7          | 5382      | H17 RT   | Inside hanger bolt connection                     | PG |
| 7          | 5383      | H17 RT   | Inside hanger bolt connection                     | PG |
| 7          | 5384      | H17 RT   | SIP deck form corrosion                           | PG |
| 7          | 5385      | H17 RT   | Floorbeam   | PG |
| 7          | 5386      | H17 RT   | Lateral bracing                                   | PG |
| 7          | 5387      | H17 RT   | Lateral bracing                                   | PG |
| 7          | 5423      | Pier 1   | Left girder bearing                               | PG |
| 7          | 5424      | Pier 1   | Heavily corroded floorbeam                        | PG |
| 7          | 5425      | Pier 1   | SIP deck form corrosion                           | PG |
| 7          | 5427      | Pier 1   | Corrosion inside left girder                      | PG |
|            |           |          |   |    |
|            |           |          |   |    |
|            |           |          |   |    |
|            |           |          |   |    |


|   |                      |                                    |  |      |             |           |           |
|---|----------------------|------------------------------------|--|------|-------------|-----------|-----------|
|  <b>kpff</b> Consulting Engineers<br>1601 Fifth Avenue, Suite 1600 Seattle, WA 98101<br>(206) 622-5822 fax (206) 622-8130 | Project              | Riverfront Park Bridges Inspection |  | By   | M. Frymoyer | Sheet No. |           |
|   | Location             | Spokane                            |  | Date | 9/26/2014   | 6 OF10    |           |
|   | Client               | City of Spokane                    |  |      |             | Job No.   |           |
|   | Inspection Photo Log |                                    |  |      |             |           | 114176.12 |

Bridge Name: North Suspension Bridge

Date of Inspection: 9/3/14-9/5/14

| Camera No. | Photo No. | Location      | Notes                               | By |
|------------|-----------|---------------|-------------------------------------|----|
| A          | 410       | H15 RT        | Top hanger to main cable connection | BK |
| A          | 411       | H15 RT        | Top hanger to main cable connection | BK |
| A          | 412       | H15 RT        | 5% loss of galvanizing              | BK |
| A          | 413       | H15 RT        | Top hanger to main cable connection | BK |
| A          | 414       | H15 LT        | Top hanger to main cable connection | BK |
| A          | 415       | H15 LT        | Top hanger to main cable connection | BK |
| A          | 416       | H15 LT        | Top hanger to main cable connection | BK |
| A          | 417       | H15 LT        | Top hanger to main cable connection | BK |
| A          | 418       | H15 LT        | Top hanger to main cable connection | BK |
| A          | 419       | H16 LT        | Top hanger to main cable connection | BK |
| A          | 420       | H16 LT        | Top hanger to main cable connection | BK |
| A          | 421       | H16 LT        | Top hanger to main cable connection | BK |
| A          | 422       | H16 LT        | Top hanger to main cable connection | BK |
| A          | 423       | H16 RT        | Top hanger to main cable connection | BK |
| A          | 424       | H16 RT        | Top hanger to main cable connection | BK |
| A          | 425       | H16 RT        | Top hanger to main cable connection | BK |
| A          | 426       | H16 RT        | Top hanger to main cable connection | BK |
|            |           |               |                                     |    |
|            |           |               |                                     |    |
| C          | 2343      | H17 RT        | Top hanger to main cable connection | PG |
| C          | 2344      | H17 RT        | Top hanger to main cable connection | PG |
| C          | 2345      | H17 RT        | Top hanger to main cable connection | PG |
| C          | 2346      | H17 RT        | Top hanger to main cable connection | PG |
| C          | 2348      | SB4 RT north  | General connection detail           | PG |
| C          | 2349      | SB4 RT north  | General connection detail           | PG |
| C          | 2350      | SB4 RT north  | General connection detail           | PG |
| C          | 2351      | SB 3 RT north | General connection detail           | PG |
| C          | 2352      | SB 3 RT north | General connection detail           | PG |
| C          | 2353      | SB3 LT north  | General connection detail           | PG |
| C          | 2354      | H17 LT        | Top hanger to main cable connection | PG |
| C          | 2355      | H17 LT        | Top hanger to main cable connection | PG |
| C          | 2356      | H17 LT        | Top hanger to main cable connection | PG |
| C          | 2357      | H17 LT        | Top hanger to main cable connection | PG |
| C          | 2358      | SB4 LT north  | General connection detail           | PG |
| C          | 2359      | SB4 LT north  | General connection detail           | PG |
| C          | 2360      | SB4 LT north  | General connection detail           | PG |
| C          | 2361      | SB3 LT north  | General connection detail           | PG |
| C          | 2362      | SB3 LT north  | General connection detail           | PG |
| C          | 2363      | SB3 LT north  | General connection detail           | PG |
| C          | 2364      | SB 3 RT north | General connection detail           | PG |
| C          | 2365      |               | General view                        | PG |
| C          | 2366      | SB2 LT north  | General connection detail           | PG |
| C          | 2367      | SB2 LT north  | General connection detail           | PG |
| C          | 2368      | SB2 LT north  | General view                        | PG |
| C          | 2369      | SB2 LT north  | General connection detail           | PG |


|   |                      |                                    |  |      |             |           |
|---|----------------------|------------------------------------|--|------|-------------|-----------|
|  <b>kpff</b> Consulting Engineers<br>1601 Fifth Avenue, Suite 1600 Seattle, WA 98101<br>(206) 622-5822 fax (206) 622-8130 | Project              | Riverfront Park Bridges Inspection |  | By   | M. Frymoyer | Sheet No. |
|   | Location             | Spokane                            |  | Date | 9/26/2014   | 7 OF10    |
|   | Client               | City of Spokane                    |  |      |             | Job No.   |
|   | Inspection Photo Log |                                    |  |      |             | 114176.12 |

Bridge Name: North Suspension Bridge

Date of Inspection: 9/3/14-9/5/14

| Camera No. | Photo No. | Location     | Notes                               | By |
|------------|-----------|--------------|-------------------------------------|----|
| C          | 2370      | SB2 LT north | General connection detail           |    |
| C          | 2371      | General      |                                     |    |
| C          | 2372      | SB2 RT north |                                     |    |
| C          | 2373      | SB2 RT north | General connection detail           |    |
| C          | 2374      | SB2 RT north | General connection detail           |    |
| C          | 2375      | SB2 RT north | General connection detail           |    |
| C          | 2376      | SB1 LT north | General connection detail           |    |
| C          | 2377      | SB1 LT north | General connection detail           |    |
| C          | 2378      | SB1 LT north | General connection detail           |    |
| C          | 2379      | SB1 LT north | General connection detail           |    |
| C          | 2380      | SB1 RT north | General connection detail           |    |
| C          | 2381      | SB1 RT north | General connection detail           |    |
| C          | 2382      | SB1 RT north | General connection detail           |    |
| C          | 2383      | North HUB    | Main suspension cable connection    |    |
| C          | 2384      | North HUB    | South side of tower connection      |    |
| C          | 2385      | North HUB    | South side of tower connection      |    |
| C          | 2386      | North HUB    | South side of tower connection      |    |
| C          | 2387      | North HUB    | South side of tower connection      |    |
| C          | 2388      | North HUB    | North side of tower connection      |    |
| C          | 2389      | North HUB    | North side of tower connection      |    |
| C          | 2390      | North HUB    | North side of tower connection      |    |
| C          | 2391      | North HUB    | North side of tower connection      |    |
| C          | 2392      | North HUB    | North side of tower connection      |    |
| C          | 2444      | H14 RT       | Top hanger to main cable connection | PG |
| C          | 2445      | H14 RT       | Top hanger to main cable connection | PG |
| C          | 2446      | H14 RT       | Top hanger to main cable connection | PG |
| C          | 2447      | H14 RT       | Top hanger to main cable connection | PG |
| C          | 2448      | H14 LT       | Top hanger to main cable connection | PG |
| C          | 2449      | H14 LT       | Top hanger to main cable connection | PG |
| C          | 2450      | H14 LT       | Top hanger to main cable connection | PG |
| C          | 2451      | H13 LT       | Top hanger to main cable connection |    |
| C          | 2452      | H13 LT       | Top hanger to main cable connection |    |
| C          | 2453      | H13 LT       | Top hanger to main cable connection |    |
| C          | 2454      | H13 RT       | Top hanger to main cable connection | PG |
| C          | 2455      | H13 RT       | Top hanger to main cable connection | PG |
| C          | 2456      | H13 RT       | Top hanger to main cable connection | PG |
| C          | 2457      | H13 RT       | Top hanger to main cable connection | PG |
|            |           |              |                                     |    |
|            |           |              |                                     |    |
| 6          | 1309      | H6 RT        | Top hanger to main cable connection | PG |
| 6          | 1310      | H6 RT        | Top hanger to main cable connection | PG |
| 6          | 1311      | H6 RT        | Top hanger to main cable connection | PG |
| 6          | 1312      | H6 RT        | Top hanger to main cable connection | PG |
| 6          | 1313      | H7 RT        | Top hanger to main cable connection | PG |
| 6          | 1314      | H7 RT        | Top hanger to main cable connection | PG |


|   |                      |                                    |  |      |             |           |           |
|---|----------------------|------------------------------------|--|------|-------------|-----------|-----------|
|  <b>kpff</b> Consulting Engineers<br>1601 Fifth Avenue, Suite 1600 Seattle, WA 98101<br>(206) 622-5822 fax (206) 622-8130 | Project              | Riverfront Park Bridges Inspection |  | By   | M. Frymoyer | Sheet No. |           |
|   | Location             | Spokane                            |  | Date | 9/26/2014   |           | 8 OF10    |
|   | Client               | City of Spokane                    |  |      |             | Job No.   |           |
|   | Inspection Photo Log |                                    |  |      |             |           | 114176.12 |

Bridge Name: North Suspension Bridge

Date of Inspection: 9/3/14-9/5/14

| Camera No. | Photo No. | Location     | Notes                               | By |
|------------|-----------|--------------|-------------------------------------|----|
| 6          | 1315      | H7 RT        | Top hanger to main cable connection | PG |
| 6          | 1316      | H8 RT        | Top hanger to main cable connection | PG |
| 6          | 1317      | H8 RT        | Top hanger to main cable connection | PG |
| 6          | 1318      | H8 RT        | Top hanger to main cable connection | PG |
| 6          | 1319      | H8 RT        | Top hanger to main cable connection | PG |
| 6          | 1320      | H9 RT        | Top hanger to main cable connection | PG |
| 6          | 1321      | H9 RT        | Top hanger to main cable connection | PG |
| 6          | 1322      | H9 RT        | Top hanger to main cable connection | PG |
| 6          | 1323      | H9 RT        | Top hanger to main cable connection | PG |
| 6          | 1324      | H10 RT       | Top hanger to main cable connection | PG |
| 6          | 1325      | H10 RT       | Top hanger to main cable connection | PG |
| 6          | 1326      | H10 RT       | Top hanger to main cable connection | PG |
| 6          | 1327      | H11 RT       | Top hanger to main cable connection | PG |
| 6          | 1328      | H11 RT       | Top hanger to main cable connection | PG |
| 6          | 1329      | H11 RT       | Top hanger to main cable connection | PG |
| 6          | 1330      | H12 RT       | Top hanger to main cable connection | PG |
| 6          | 1331      | H12 RT       | Top hanger to main cable connection | PG |
| 6          | 1332      | H12 RT       | Top hanger to main cable connection | PG |
| 6          | 1333      | H12 RT       | Top hanger to main cable connection | PG |
|            |           |              |                                     |    |
|            |           |              |                                     |    |
| 7          | 5333      | H1 RT        | Top hanger to main cable connection | PG |
| 7          | 5334      | H1 RT        | Top hanger to main cable connection | PG |
| 7          | 5335      | H1 RT        | Top hanger to main cable connection | PG |
| 7          | 5336      | H1 RT        | Top hanger to main cable connection | PG |
| 7          | 5337      | H1 RT        | Top hanger to main cable connection | PG |
| 7          | 5338      | SB3 RT south | General view of spreader bars       | PG |
| 7          | 5339      | H1 LT        | Top hanger to main cable connection | PG |
| 7          | 5340      | H1 LT        | Top hanger to main cable connection | PG |
| 7          | 5341      | H1 LT        | Top hanger to main cable connection | PG |
| 7          | 5342      | H1 LT        | Top hanger to main cable connection | PG |
| 7          | 5343      | H1 LT        | Top hanger to main cable connection | PG |
| 7          | 5344      | H1 LT        | Top hanger to main cable connection | PG |
| 7          | 5345      | SB3 LT south | General connection detail           | PG |
| 7          | 5346      | SB3 RT south | General connection detail           | PG |
| 7          | 5351      | SB2 RT south | General connection detail           | PG |
| 7          | 5352      | SB2 RT south | General connection detail           | PG |
| 7          | 5353      | SB2 LT south | General connection detail           | PG |
| 7          | 5354      | SB2 LT south | General connection detail           | PG |
| 7          | 5355      | SB1 RT south | General connection detail           | PG |
| 7          | 5356      | SB1 RT south | General connection detail           | PG |
| 7          | 5357      | SB1 RT south | General connection detail           | PG |
| 7          | 5358      | SB1 RT south | General connection detail           | PG |
| 7          | 5359      | SB1 LT south | General connection detail           | PG |
| 7          | 5360      | SB1 LT south | General connection detail           | PG |

|   |                      |                                    |  |      |             |           |           |
|---|----------------------|------------------------------------|--|------|-------------|-----------|-----------|
|  <b>kpff</b> Consulting Engineers<br>1601 Fifth Avenue, Suite 1600 Seattle, WA 98101<br>(206) 622-5822 fax (206) 622-8130 | Project              | Riverfront Park Bridges Inspection |  | By   | M. Frymoyer | Sheet No. |           |
|   | Location             | Spokane                            |  | Date | 9/26/2014   |           | 9 OF10    |
|   | Client               | City of Spokane                    |  |      |             | Job No.   |           |
|   | Inspection Photo Log |                                    |  |      |             |           | 114176.12 |


  

Bridge Name: North Suspension Bridge

Date of Inspection: 9/3/14-9/5/14

| Camera No. | Photo No. | Location     | Notes   | By  |
|------------|-----------|--------------|---|-----|
| 7          | 5362      | SB1 LT south | General connection detail                               | PG  |
| 7          | 5363      | South HUB    | Main suspension cable connection                        | PG  |
| 7          | 5364      | South HUB    | Main suspension cable connection                        | PG  |
| 7          | 5365      | South HUB    | Main suspension cable connection                        | PG  |
| 7          | 5388      | General      | Ladder access for interior hanger connection inspection | MLF |
| 7          | 5389      | General      | Ladder access for interior hanger connection inspection | MLF |
| 7          | 5390      | General      | Ladder access for interior hanger connection inspection | MLF |
| 7          | 5391      | H5 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5392      | H5 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5393      | H5 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5394      | H5 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5395      | H5 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5396      | H5 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5397      | H4 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5398      | H4 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5399      | H4 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5400      | H4 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5401      | H4 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5402      | H4 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5403      | H4 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5404      | H4 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5405      | H4 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5406      | H3 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5407      | H3 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5408      | H3 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5409      | H3 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5410      | H3 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5411      | H3 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5412      | H3 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5413      | H3 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5414      | H2 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5415      | H2 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5416      | H2 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5417      | H2 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5418      | H2 RT        | Top hanger to main cable connection                     | PG  |
| 7          | 5419      | H2 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5420      | H2 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5421      | H2 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5422      | H2 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5509      | H6 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5510      | H6 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5511      | H6 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5512      | H7 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5513      | H7 LT        | Top hanger to main cable connection                     | PG  |
| 7          | 5514      | H7 LT        | Top hanger to main cable connection                     | PG  |



|   |                      |                                    |  |      |             |           |           |
|---|----------------------|------------------------------------|--|------|-------------|-----------|-----------|
|  <b>kpff</b> Consulting Engineers<br>1601 Fifth Avenue, Suite 1600 Seattle, WA 98101<br>(206) 622-5822 fax (206) 622-8130 | Project              | Riverfront Park Bridges Inspection |  | By   | M. Frymoyer | Sheet No. |           |
|   | Location             | Spokane                            |  | Date | 9/26/2014   |           | 10 OF10   |
|   | Client               | City of Spokane                    |  |      |             | Job No.   |           |
|   | Inspection Photo Log |                                    |  |      |             |           | 114176.12 |

Bridge Name: North Suspension Bridge

Date of Inspection: 9/3/14-9/5/14

| Camera No. | Photo No. | Location  | Notes                                     | By  |
|------------|-----------|-----------|---|-----|
| 7          | 5515      | H8 LT     | Top hanger to main cable connection       | PG  |
| 7          | 5516      | H8 LT     | Top hanger to main cable connection       | PG  |
| 7          | 5517      | H8 LT     | Top hanger to main cable connection       | PG  |
| 7          | 5518      | H9 LT     | Top hanger to main cable connection       | JPG |
| 7          | 5519      | H9 LT     | Top hanger to main cable connection       | JPG |
| 7          | 5520      | H9 LT     | Top hanger to main cable connection       | JPG |
| 7          | 5521      | H10 LT    | Top hanger to main cable connection       | JPG |
| 7          | 5522      | H10 LT    | Top hanger to main cable connection       | JPG |
| 7          | 5523      | H10 LT    | Top hanger to main cable connection       | JPG |
| 7          | 5524      | H10 LT    | Cotter pins needs to be replaced          | JPG |
| 7          | 5525      | H11 LT    | Top hanger to main cable connection       | JPG |
| 7          | 5526      | H11 LT    | Top hanger to main cable connection       | JPG |
| 7          | 5527      | H11 LT    | Top hanger to main cable connection       | JPG |
| 7          | 5528      | H12 LT    | Top hanger to main cable connection       | JPG |
| 7          | 5529      | H12 LT    | Top hanger to main cable connection       | JPG |
| 7          | 5530      | H12 LT    | Top hanger to main cable connection       | JPG |
|            |           |           |   |     |
| 2          | 44        | NW Anchor | Top view of anchorage                     | TW  |
| 2          | 45        | NW Anchor | Cable / nuts                              | TW  |
| 2          | 46        | NW Anchor | Cable / nuts                              | TW  |
| 2          | 47        | NW Anchor | Cable / nuts                              | TW  |
| 2          | 48        | NW Anchor | Cable anchorage                           | TW  |
| 2          | 50        | NW Anchor | Tree growth around cable                  | TW  |
| 2          | 51        | NW Anchor | Tree growth around cable                  | TW  |
| 2          | 52        | NW Anchor | Cable                                     | TW  |
| 2          | 53        | General   | Climbing access for under deck inspection | TW  |
| 2          | 54        | General   | Climbing access for under deck inspection | TW  |
| 2          | 55        | NE Anchor | Anchorage block                           | TW  |
| 2          | 56        | NE Anchor | Anchorage block                           | TW  |
| 2          | 57        | NE Anchor | Anchorage nuts                            | TW  |
| 2          | 58        | NE Anchor | 1/4" movement at cable anchorage          | TW  |
| 2          | 59        | NE Anchor | Threaded rods in contact with soil        | TW  |
| 2          | 60        | NE Anchor | Cable anchorage                           | TW  |
| 2          | 61        | NE Anchor | Cable                                     | TW  |
| 2          | 62        | NE Anchor | Cable                                     | TW  |
| 2          | 63        | NE Anchor | Anchorage block                           | TW  |
| 2          | 64        | SE Anchor | Shrubs growing around anchorage block     | TW  |
| 2          | 65        | SE Anchor | Shrubs growing around anchorage block     | TW  |
| 2          | 66        | SE Anchor | Cable                                     | TW  |
| 2          | 71        | SW Anchor | Shrubs growing around anchorage block     | TW  |
| 2          | 72        | SW Anchor | Upper lock nut is not fully engaged       | TW  |
| 2          | 73        | SW Anchor | Upper lock nut is not fully engaged       | TW  |
| 2          | 75        | SW Anchor | Cable                                     | TW  |
| 2          | 76        | SW Anchor | Cable                                     | TW  |
| 2          | 77        | SW Anchor | Anchorage block                           | TW  |





## North Suspension Bridge - Camera A Photos



IMG\_0358.JPG



IMG\_0359.JPG



IMG\_0361.JPG



IMG\_0362.JPG



IMG\_0368.JPG



IMG\_0369.JPG



IMG\_0370.JPG



IMG\_0372.JPG



IMG\_0373.JPG



IMG\_0374.JPG



IMG\_0375.JPG



IMG\_0376.JPG



IMG\_0377.JPG



IMG\_0378.JPG



IMG\_0379.JPG



IMG\_0380.JPG




IMG\_0381.JPG



IMG\_0382.JPG



IMG\_0383.JPG



IMG\_0384.JPG



IMG\_0385.JPG



IMG\_0386.JPG



IMG\_0387.JPG



IMG\_0389.JPG



IMG\_0390.JPG



IMG\_0392.JPG



IMG\_0393.JPG



IMG\_0394.JPG



IMG\_0395.JPG



IMG\_0396.JPG



IMG\_0397.JPG




IMG\_0398.JPG



IMG\_0399.JPG



IMG\_0401.JPG



IMG\_0402.JPG



## North Suspension Bridge - Camera A Photos



IMG\_0403.JPG



IMG\_0404.JPG



IMG\_0405.JPG



IMG\_0406.JPG



IMG\_0407.JPG



IMG\_0408.JPG



IMG\_0409.JPG



IMG\_0427.JPG



IMG\_0428.JPG



IMG\_0429.JPG




IMG\_0430.JPG

## North Suspension Bridge - Camera C Photos



IMG\_2321.JPG



IMG\_2297.JPG



IMG\_2298.JPG



IMG\_2299.JPG



IMG\_2300.JPG



IMG\_2301.JPG



IMG\_2302.JPG



IMG\_2303.JPG



IMG\_2304.JPG



IMG\_2305.JPG



IMG\_2306.JPG



IMG\_2307.JPG



IMG\_2309.JPG




IMG\_2310.JPG



IMG\_2311.JPG



IMG\_2312.JPG



IMG\_2313.JPG



IMG\_2314.JPG



IMG\_2315.JPG



IMG\_2316.JPG



IMG\_2317.JPG



IMG\_2318.JPG



IMG\_2319.JPG



IMG\_2320.JPG



## North Suspension Bridge - Camera 6 Photos



IMG\_1308.JPG



IMG\_1215.JPG



IMG\_1216.JPG



IMG\_1218.JPG



IMG\_1219.JPG



IMG\_1220.JPG



IMG\_1221.JPG



IMG\_1222.JPG



IMG\_1223.JPG




IMG\_1224.JPG



IMG\_1225.JPG



IMG\_1226.JPG



IMG\_1227.JPG



IMG\_1228.JPG



IMG\_1229.JPG



IMG\_1230.JPG



IMG\_1231.JPG



IMG\_1232.JPG



IMG\_1233.JPG



IMG\_1234.JPG



IMG\_1235.JPG



IMG\_1236.JPG



IMG\_1237.JPG



IMG\_1240.JPG



IMG\_1241.JPG



IMG\_1242.JPG




IMG\_1248.JPG




IMG\_1249.JPG




IMG\_1250.JPG



IMG\_1251.JPG



IMG\_1252.JPG



IMG\_1253.JPG



IMG\_1254.JPG



IMG\_1255.JPG



IMG\_1256.JPG



## North Suspension Bridge - Camera 6 Photos



IMG\_1257.JPG



IMG\_1258.JPG



IMG\_1259.JPG



IMG\_1260.JPG



IMG\_1261.JPG



IMG\_1262.JPG



IMG\_1263.JPG



IMG\_1264.JPG



IMG\_1265.JPG



IMG\_1266.JPG



IMG\_1267.JPG



IMG\_1268.JPG



IMG\_1269.JPG



IMG\_1270.JPG



IMG\_1271.JPG



IMG\_1272.JPG



IMG\_1273.JPG



IMG\_1274.JPG



IMG\_1275.JPG



IMG\_1276.JPG



IMG\_1277.JPG



IMG\_1278.JPG



IMG\_1279.JPG



IMG\_1280.JPG



IMG\_1281.JPG



IMG\_1282.JPG



IMG\_1283.JPG



IMG\_1284.JPG



IMG\_1285.JPG



IMG\_1286.JPG




IMG\_1287.JPG



IMG\_1288.JPG



IMG\_1289.JPG



IMG\_1290.JPG



IMG\_1291.JPG



## North Suspension Bridge - Camera 6 Photos



IMG\_1292.JPG



IMG\_1293.JPG



IMG\_1294.JPG



IMG\_1295.JPG



IMG\_1296.JPG



IMG\_1297.JPG



IMG\_1298.JPG



IMG\_1299.JPG



IMG\_1300.JPG



IMG\_1301.JPG



IMG\_1302.JPG



IMG\_1303.JPG



IMG\_1304.JPG



IMG\_1305.JPG



IMG\_1306.JPG



IMG\_1307.JPG





## North Suspension Bridge - Camera A Photos Cables



IMG\_0426.JPG



IMG\_0410.JPG



IMG\_0411.JPG



IMG\_0412.JPG



IMG\_0413.JPG



IMG\_0414.JPG



IMG\_0415.JPG




IMG\_0416.JPG



IMG\_0417.JPG



IMG\_0418.JPG



IMG\_0419.JPG



IMG\_0420.JPG



IMG\_0421.JPG




IMG\_0422.JPG



IMG\_0423.JPG



IMG\_0424.JPG



IMG\_0425.JPG



## North Suspension Bridge - Camera C Photos Cables



IMG\_2457.JPG



IMG\_2343.JPG



IMG\_2344.JPG



IMG\_2345.JPG



IMG\_2346.JPG



IMG\_2348.JPG



IMG\_2349.JPG



IMG\_2350.JPG



IMG\_2351.JPG



IMG\_2352.JPG



IMG\_2353.JPG



IMG\_2354.JPG



IMG\_2355.JPG



IMG\_2356.JPG



IMG\_2357.JPG




IMG\_2358.JPG



IMG\_2359.JPG



IMG\_2360.JPG



IMG\_2361.JPG



IMG\_2362.JPG



IMG\_2363.JPG



IMG\_2364.JPG



IMG\_2365.JPG



IMG\_2366.JPG



IMG\_2367.JPG



IMG\_2368.JPG



IMG\_2369.JPG



IMG\_2370.JPG



IMG\_2371.JPG



IMG\_2372.JPG



IMG\_2373.JPG



IMG\_2374.JPG



IMG\_2375.JPG



IMG\_2376.JPG



IMG\_2377.JPG



## North Suspension Bridge - Camera C Photos Cables



IMG\_2378.JPG



IMG\_2379.JPG



IMG\_2380.JPG



IMG\_2381.JPG



IMG\_2382.JPG



IMG\_2383.JPG



IMG\_2384.JPG



IMG\_2385.JPG



IMG\_2386.JPG




IMG\_2387.JPG



IMG\_2388.JPG



IMG\_2389.JPG



IMG\_2390.JPG



IMG\_2391.JPG



IMG\_2392.JPG



IMG\_2444.JPG



IMG\_2445.JPG



IMG\_2446.JPG



IMG\_2447.JPG



IMG\_2448.JPG



IMG\_2449.JPG



IMG\_2450.JPG



IMG\_2451.JPG



IMG\_2452.JPG



IMG\_2453.JPG



IMG\_2454.JPG



IMG\_2455.JPG



IMG\_2456.JPG















North Suspension Bridge - Camera 7 Photos Cables



IMG\_5515.JPG



IMG\_5516.JPG



IMG\_5517.JPG



IMG\_5518.JPG



IMG\_5519.JPG



IMG\_5520.JPG



IMG\_5521.JPG



IMG\_5522.JPG



IMG\_5523.JPG



IMG\_5524.JPG



IMG\_5525.JPG



IMG\_5526.JPG



IMG\_5527.JPG



IMG\_5528.JPG



IMG\_5529.JPG



## North Suspension Bridge - Camera 2 Photos



IMG\_0044.JPG



IMG\_0045.JPG



IMG\_0046.JPG



IMG\_0047.JPG



IMG\_0048.JPG



IMG\_0050.JPG




IMG\_0051.JPG



IMG\_0052.JPG



IMG\_0053.JPG



IMG\_0054.JPG



IMG\_0055.JPG



IMG\_0056.JPG



IMG\_0057.JPG



IMG\_0058.JPG



IMG\_0059.JPG



IMG\_0060.JPG



IMG\_0061.JPG



IMG\_0062.JPG



IMG\_0063.JPG



IMG\_0064.JPG



IMG\_0065.JPG



IMG\_0066.JPG



IMG\_0071.JPG



IMG\_0072.JPG



IMG\_0073.JPG



IMG\_0075.JPG



IMG\_0076.JPG



IMG\_0077.JPG

|                      |                                    |      |             |           |
|----------------------|------------------------------------|------|-------------|-----------|
| Project              | Riverfront Park Bridges Inspection | By   | M. Frymoyer | Sheet No. |
| Location             | Spokane                            | Date | 9/26/2014   | 1 OF1     |
| Client               | City of Spokane                    |      |             | Job No.   |
| Inspection Photo Log |                                    |      |             | 114176.12 |

Bridge Name: South Suspension Bridge Vaults

Date of Inspection: 9/2/14-9/5/14

[illegible]



## North Suspension Bridge Vaults - Photos



IMG\_0295.JPG



IMG\_0278.JPG



IMG\_0279.JPG



IMG\_0280.JPG



IMG\_0281.JPG



IMG\_0282.JPG



IMG\_0283.JPG



IMG\_0284.JPG




IMG\_0285.JPG



IMG\_0286.JPG



IMG\_0288.JPG




IMG\_0289.JPG




IMG\_0290.JPG



IMG\_0291.JPG



IMG\_0292.JPG



IMG\_0293.JPG



IMG\_0294.JPG