



TRIM ONLY DEAD OR BROKEN BRANCHES AND DOUBLE LEADERS AT THE TIME OF PLANTING.

COMPLETELY REMOVE WIRE BASKETS AND OR BURLAP FROM ROOT BALL.

PEA GRAVEL MULCH TO BOTTOM OF GRATE, LEAVE SPACE FOR IRRIGATION EMITTERS, SEE SPECIFICATIONS FOR MORE INFORMATION.

SOIL UNDER ROOTBALL SHALL BE LIGHTLY COMPACTED TO REDUCE SETTLING.

IRRIGATION EMITTER, LOCATED IN EACH CORNER, SEE IRRIGATION DRAWINGS FOR MORE INFORMATION.

REMOVE ALL TREE WRAP.

ROOT FLARE SHALL BE 1-2" ABOVE TOP OF GRADE, REMOVE EXCESS SOIL FROM ROOTBALL AS NEEDED TO EXPOSE ORIGINAL ROOT FLARE.

KEEP MULCH BACK FROM TRUNK, ENDING AT EDGE OF EXPOSED ROOT BALL.

TREE GRATE SEE OTHER DETAIL

BACK FILL WITH APPROVED SOIL MIX, WATER THOROUGHLY, DO NOT TAMP. SLOPE FROM TOP OF ROOT BALL TO APPROX. 3" BELOW GRATE NEAR EDGES.

UNDISTURBED SOIL
IRRIGATION MAINLINE
STRUCTURAL FILL BY OTHERS

NOTES:

1. TREES BURIED TOO DEEP, OR WITHOUT EXPOSING ROOT FLARE WILL BE REJECTED, REMOVED AND REPLANTED AT APPROPER DEPTH.
2. ALL 'ADVENTITIOUS ROOTS' AND 'SUCKERS' SHALL BE TRIMMED AWAY PRIOR TO PLANTING.
3. DEVIATIONS FROM THIS DETAIL SHALL ONLY BE ALLOWED WITH WRITTEN PERMISSION BY THE CITY OF SPOKANE'S URBAN FORESTER.

